

15-051-19287-0008

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION CN $\frac{1}{2}$  NE NE

SEC. 27 TWP. 12 RGE. 18

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Joy

Operator Petroleum Inc Address Wichita, Kans

Field \_\_\_\_\_ County Ellis

Total Depth 3716 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 165' circulated with cement - 5 1/2" at 3709' with 80 sax  
cement behind.

Filled with chat to 3700', set 4 sax cement with dump bailer,  
pulled 3100' 5 1/2", filled hole with mud to 165', set rock bridge  
and 15 sax cement, filled with mud to 35', set rock and 10 sax  
cement to bottom cellar.

**RECEIVED**

STATE CORPORATION COMMISSION

OCT 13 1951

CONSERVATION DIVISION

Wichita, Kansas

*Eldon Kelly*  
District Conservation Agent

Date 10-8-51

PLUGGING

FILE SEC 27 TWP 12 R 18  
BOOK PAGE 115 LINE 37