

15-055-30011-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Shallow Water Refining Company

Complete Address: 1325' Wichita, ~~Kansas~~/Plaza, Wichita, Kansas

Lease Name Jennings Well No. 1

Location C NE NE Sec. 1 Twp. 22 Rge. 34 ~~(E)~~ (W)

County Finney Total Depth 4832'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405, Ghase, Kansas License No. 436

Operation Completed: Hour 5:00PM Day 11 Month 9 Year 1967

The Above well was plugged as follows:

8 5/8" to 428' circulated w/ cement. 5 1/2" to 4830' cemented.

Plug back 4040' Top perforations 3994'

Plug bottom w/ sand & 5 sacks cement. Top of cement 3900'

Mud 3900' to 425' Rock bridge & 35 sacks cement 425' to 3250'

Mud 325' to 35' Plug, Halls & 10 sacks cement 35' to 0'

Pulled 982' of 5 1/2" casing.

RECEIVED
STATE CORPORATION COMMISSION

SEP 14 1967

I hereby certify that the above well was plugged as shown on the DIVISION

INVOICED

Wichita, Kansas
Signed: Edmond A. Eves
Well Plugging Supervisor

DATE 9/14/67

INV. NO. 6331-W

DRILLER'S LOG

COMPANY:
 CONTRACTOR:
 FARM:
 LOCATION:
 COMMENCED:
 COMPLETED:

R. W. Lange
 LEBEN DRILLING, INC.
 JENNINGS #1
 C NE NE Sec. 1-22S-34W
 FINNEY COUNTY, KANSAS
 5-10-65
 6-1-65

0 145
 145 620
 620 1526
 1526 2890
 2890 3105
 3105 3580
 3580 3695
 3695 4030
 4030 4390
 4390 4440
 4440 4515
 4515 4564
 4564 4609
 4609 4780
 4780 4832
4832

Shale & Gypsum rock
 Shale
 Shale & Redbed
 Shale
 Shale & Lime
 Lime & Shale
 Lime
 Lime & Shale
 Lime
 Core
 Lime
 Core
 Lime
 Core
 Lime
RTD - Set 5 1/2" Casing

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 20 1967
 CONSERVATION DIVISION
 Wichita, Kansas

8 5/8" used surface casing set @ 428' with 300 sacks Common 3% HAS cement did not circulate so ran 1 1/2" tubing down outside of 8 5/8", cement within 3' of cellar

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Jennings #1 well, located C NE NE of Section 1, Township 22 South, Range 34 West, Finney County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite

 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 3rd day of June, 1965.

Ulanda Nichols

 Ulanda Nichols