

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 7 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Graybol Oil Corporation

Complete Address: 2200 National Bank of Tulsa Bldg., Tulsa, Oklahoma

Lease Name Flora Well No. # 1

Location C NW NW Sec. 24 Twp. 29 Rge. 13 (E) (W) W

County Pratt Total Depth 4730'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Graybol Oil Corporation

Address: 2200 National Bank of Tulsa Bldg., Tulsa, Okla License No. _____

Operation Completed: Hour 7:00PM Day 3rd Month July Year 1966

The Above well was plugged as follows:

369' of 8 5/8" surface pipe, cement circulated with 275 sacks. Fluid level in the hole was at 197'. 1st cementing plug and 1/2 sack of hulls was pushed in fluid to 325', and cemented with 25 sacks, through the drill pipe. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed:

Archie Elving
Well Plugging Supervisor

DATE 7-7-66

INV. NO. 3576-W