

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-151-20, 686⁰⁰⁻⁰⁰

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name FXO Production Corporation

Complete Address 200 W. Douglas, Ste 300 Wichita 67202

Lease Name Shiles Well No. 1

Location 1320' Fml + 1980' FEL Sec. 24 Twp. 29S Rge. 13 (East) (West)

County Pratt Total Depth 4732'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service

Address Box 847 Pratt, Kansas 67124 License No. _____

Operation Completed: Hour: 9³⁰ AM Day: 21 Month: 6 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

5 1/2" cas. 4723' w/150 sf
PS to 4600' Lap Perf 4516'-4522'
SB to 4485' + 5 sf
Pump 1 1/2 gal 6 shells 10 gal
Release Plug + displace w/175 sf Cement 390 c.c
Sum 510-200^{##}

Amount of Surface Casing: 234' of 10 3/4" w/325

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

STATE CORPORATION COMMISSION
RECEIVED
JULY 28 1982
06-28-82

INVOICED

DATE 6-29-82

INV. NO. 544-W

Signed: _____
Conservation Division Agent
Wichita Kansas

KANSAS DRILLERS LOG

COMPANY Texas Oil & Gas Corp.

SEC. 24 T. 29S R. 13W

FARM Skiles NO. 1

LOC. 1320' FNL & 1980'

FEI

COUNTY Pratt

ROTARY TOTAL DEPTH 4,732'

COMM. October 22, 1979 COMP. November 4, 1979

CONTRACTOR H-30, Inc. (Rig #5)

ISSUED November 13, 1979

CASING

10 3/4" Set at 236' cemented w/325 sxs cement

8 5/8"

ELEVATION 1,928' K.B.

5 1/2" Set at 4,729' cemented w/150 sxs cement

4 1/2"

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed and Sand	257'
Red Bed and Shale	625'
Red Bed	1,412'
Shale	1,849'
Lime and Shale	2,382'
Shale and Lime	2,825'
Lime and Shale	3,044'
Shale and Lime	3,525'
Lime and Shale	3,746'
Shale and Lime	3,802'
Lime and Shale	3,815'
Shale and Lime	4,005'
Lime and Shale	4,246'
Shale and Lime	4,405'
Lime and Shale	4,712'
Shale and Lime	4,732'
Rotary Total Depth	4,732'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

RECEIVED
STATE CORPORATION COMMISSION
5-17-82
MAY 17 1982
CONSERVATION DIVISION
Wichita, Kansas

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 13th day of November, 1979.

Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982