


WELL PLUGGING RECORD

City All Information Completely
Map Required Address
M.A. or Address Report to
Conservation Division
State Corporation Commission
Bill No. Inventory
Wichita, Kansas

Pratt

County. Sec. 1 Twp. 26 Rge. (E) 15(W)

Location as "NE/CNW/SW" or footage from lines SW SE
Lease Owner: Schermerhorn Oil Corp. & Strata Drilling, Inc.
Lease Name: Parks Well No. 2
Office Address: P. O. Box 287, Tulsa 1, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 18 1962
Application for plugging filed February 18 1962
Application for plugging approved February 18 1962
Plugging commenced February 18 1962
Plugging completed February 18 1962
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plot

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation Depth to top Bottom Total Depth of Well 4485 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	280	0			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged as follows: Plugged at 270' with 20 sacks of cement and 1/4 sack of hulls to 40'; plugged with 10 sacks of cement and 1/4 sack of hulls. Plugged rathole with 2 sacks of cement. Job completed at 10:00 A. M. February 18, 1962.

RECORDED
INDEXED
STATE CORPORATION COMMISSION

FEB 21 1962

CONSERVATION DIVISION
Wichita, Kansas

2-21-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas

STATE OF KANSAS COUNTY OF BARTON
Jim B. McWilliams (employee or owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim B. McWilliams
Box 355, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of February, 1962

My commission expires December 14, 1965

Elaine H. Taylor
Notary Public.

D R I L L E R S L O G

#2 Parks

CASING RECORD:
288' new 8-5/8"
surface casing

COMPANY: Schermerhorn Oil Corp. &
Strata Drilling, Inc.
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: SW SE
Section 1-26-15W
Pratt County, Kansas

TOTAL DEPTH:
4485'

COMMENCED: February 6, 1962
COMPLETED: February 18, 1962

ELEVATION: 2026' RB

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay, Sand & Clay	0	250	Ran 280' of new 8-5/8" surface casing; set and cemented at 288 with 250 sacks of regular cement, 2% gel and 2% C. C. Plug down @ 1:15 A. M. 2-7-62. Did not circulate cement. Cemented through 1" pipe with 80 sacks of cement.
Red Bed	250	289	
Shale	289	928	
Anhydrite	928	940	
Shale & Shells	940	1705	
Shale	1705	1855	
Lime & Shale	1855	3370	
Lime	3370	3473	
Lime & Shale	3473	3780	
Lime	3780	4180	
Lime & Chert	4180	4241	
Chert & Shale	4241	4297	
Lime & Chert	4297	4420	
Shale & Lime	4420	4485	

Total Depth 4485'

RECEIVED
STATE COMMISSION

FEB 21 1962

CONSERVATION DIVISION
Wichita

Ran Schlumberger log.


D. & A.

Plugged as follows; plugged with 20 sacks of cement and 1/4 sack of hulls to 270'; plugged with 10 sacks of cement and 1/4 sack of hulls to 40'. Plugged rathole with 2 sacks of cement. Job completed at 10:00 A. M. February 18, 1962.


STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.


Jim B. McWilliams, Secy-Treas.

Subscribed and sworn to before me this 19th day of February, 1962.


Elaine H. Taylor, Notary Public

My Commission Expires:
December 14, 1965