


15-151-00435.00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Pratt County, Sec. 1 Twp. 26 Rge. 15 (E) (W) X

Location as "NE/CNW/SW" or footage from lines NW SE SE

Lease Owner Jenkins - Ray Supply, Inc.

Lease Name Park Well No. 1

Office Address P. O. Box 1960 Ponca City, Oklahoma 74601

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved April 21, 1970 19

Plugging commenced May 2, 1970 19

Plugging completed May 9, 1970 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation Depth to top Bottom Total Depth of Well 4480 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	289	None
				5 1/2	None	2483'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Moved unit into location, rigged up pole and drove stakes. Cleaned cellar, unpacked head, set in sills, jacks and spiders. Took slips out of head. Plug off bottom with 100 gals of sand and 5 sacks of cement to 4385'. Had 22" tension at 2,500 psi or 110,000 lbs.

Shot off pipe at 3312', 3000' and 2818'. Working pipe, pipe moving very slow. Pulling at 3200 and 3300 psi on gauge, laid down starting nipple. Pipe still not free, moving 1/2" to 1" at a time, left jacks set on pressure over night.

Working pipe till 10:30. Shot pipe at 2694' and 2460' and worked pipe loose. Laid down 31 joints of 5 1/2" pipe. Laid down 20 joints of 5 1/2" pipe.

Finished laying down pipe, 30 more joints. Loaded out trailer. Pushed plug to 280', dumped 10' rock bridge and 25 sacks of cement. Mudded hole to 30' and dumped 10 sacks of cement to base of cellar.

Laid down pole, loaded unit, cleaned up around lease and moved off location.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 25 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Forbes Casing Pulling Company, Inc.  
Address P. O. Box 221 Great Bend, Kansas


STATE OF Kansas, COUNTY OF Barton, ss. James W. Rockhold (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
P. O. Box 221 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 19 day of May, 1970

My commission expires May 27, 1973 Notary Public.



D R I L L E R S L O G

#1 Parks

CASING RECORD:  
289' of 8-5/8"  
surface casing

COMPANY: Schermerhorn Oil Corp. &  
Strata Drilling, Inc.  
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: NW SE SE  
Section 1-26-15W  
Pratt County, Kansas

TOTAL DEPTH:  
4480'

COMMENCED: November 4, 1961

ELEVATION: 2018' RB

COMPLETED: November 18, 1961

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay & Sand	0	240	Ran 289' of 8-5/8" surface casing; set and cemented at 288' with 100 sacks of cement, 2% gel and 2% C. C. & 180 sacks of cement, 4% gel and 2% C. C. Plug down at 12:30 A. M. 11-5-1961.
Shale	240	289	
Red Bed & Shale	289	970	
Red Bed & Shale	970	1390	
Lime & Shale	1390	3830	
Lime	3830	4065	
Lime & Shale	4065	4249	
Lime & Chert	4249	4274	
Lime, Chert & Shale	4274	4332	
Cherty Lime	4332	4358	
Lime, Shale & Chert	4358	4368	
Chert & Lime	4368	4410	
Lime	4410	4420	
Shale & Sand	4420	4450	
Lime	4450	4480	

Total Depth 4480'

Ran Schlumberger Log.

RECEIVED  
STATE CORPORATION COMMISSION  
APR 21 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Ran 146 Joints of new 5 1/2" casing; set and cemented at 4479' with 225 sacks of 50-50 posmix, 2% gel and 18 lbs. salt per sack of cement. Plug down @ 11:10 P. M. 11-18-1961.

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON )

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

*Jim B. McWilliams*  
Jim B. McWilliams, Secy-Treas.

Subscribed and sworn to before me this 22nd day of November, 1961.

*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public

My Commission Expires:  
December 14, 1961