


STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

### WELL PLUGGING RECORD

Pratt County, Sec. 3 Twp. 29 Rge. (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines NE 1/4 NE 1/4 NW 1/4  
Lease Owner Lewis Drilling Company, et al  
Lease Name Eads Well No. 1  
Office Address 607 Union National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 7-4-19 55  
Application for plugging filed 7-4-19 55  
Application for plugging approved 7-5-19 55  
Plugging commenced 7-5-19 55  
Plugging completed 7-5-19 55  
Reason for abandonment of well or producing formation \_\_\_\_\_



Locate well correctly on above Section Flat.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4716 Feet  
Show depth and thickness of all water, oil and gas formations.

#### OIL, GAS OR WATER RECORDS

#### CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	315'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Run pipe 1/2 way in hole, circulate to displace hole, come out, lay down drill pipe, fill hole to 300' with heavy, then plug with 1/2 Sx. Halls and 20 Sx. cement mixed through drill pipe, run heavy mud to 40', plug and 1/2 Sx. Halls & 10 Sx. Cement to bottom of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lewis Drilling Company  
Address 607 Union National Bank Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
L. L. Bailey (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. L. Bailey  
607 Union National Bank Bldg., Wichita, Kans.  
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of July, 19 55

My commission expires August 20, 1956  
Arthur P. Derrington Notary Public.

**PLUGGING**  
FILE SEC 3 T 29 R 14 W  
BOOK 37 PAGE 37 LINE 37

REC  
STATE CORP  
JUL 15 1955 07-15-55  
CONSERVATION DIVISION  
Wichita, Kansas

# WELL LOG

COMPANY Lewis Drilling Company, et al

SEC. 3 T. 29 R. 14W

FARM Eads

NO. 1

LOC.

NE  $\frac{1}{4}$  NE  $\frac{1}{4}$  NW  $\frac{1}{4}$

TOTAL DEPTH 4716'

COMM. 6-18-55


COMP. 7-1-55

COUNTY Pratt  
KANSAS

SHOT OR TREATED

CONTRACTOR Lewis Drilling Company

ISSUED



CASING

20	10		
15	8-5/8"	315'	
12	6		
13	5		

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

0 -	40	Surface Clay
40 -	110	Sand & Gravel
110 -	200	Sand & Clay
200 -	425	Red Bed
425 -	1450	Sand & Shale
1450 -	1920	Shale & Shells
1920 -	1990	Shale
1990 -	2265	Lime & Shale
2265 -	2370	Lime
2370 -	2910	Lime & Shale
2910 -	3090	Shale
3090 -	3620	Lime & Shale
3620 -	3750	Lime
3750 -	3900	Lime & Shale
3900 -	3980	Shale
3980 -	3999	Brown Lime
3999 -	4045	Lans. K.C. Lime
4045 -	4115	Lime
4115 -	4175	Lime & Shale
4175 -	4192	Lime
4192 -	4425	Lime & Shale
4425 -	4610	Lime & Chert
4610 -	4620	Lime
4620 -	4656	Lime, Shale & Chert
4656 -	4690	Lime & Shale
4690 -	4716	Lime & Arbuckle
4716	T.D.	

RECEIVED  
 STATE OF KANSAS  
 CONSERVATION  
 WATER

State of KANSAS }  
 County of SEDGWICK } ss:

**PLUGGING**  
 FILE SEC 3 T 29 R 14W  
 BOOK PAGE 31 LINE 37

I, L. L. Bailey of the Lewis Drilling Company

upon oath state that the above and foregoing is a true and correct copy of the log of the Eads #1 well.

*L. L. Bailey*

Subscribed and sworn to before me this 12th day of July 19 55

My Commission Expires: August 20, 1956

*Arthur P. Derrington*  
 NOTARY PUBLIC