


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittig Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

PRATT County. Sec. 1 Twp. 29 Rge. (E) 14 (W)
Location as "NE/CNW/SW" or footage from lines SE SW SE
Lease Owner R. L. Ferguson & Musgrove Petroleum Corp.
Lease Name MOORE A Well No. 1
Office Address 518 Petroleum Building, Wichita, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed September 5, 1954
Application for plugging filed verbally - September 5, 1954
Application for plugging approved verbally - September 5, 1954
Plugging commenced September 5, 1954
Plugging completed September 5, 1954
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes, written 9-8-54

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Kansas.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4705 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	338'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 300'
Set first plug at 300' with 20 sx cement.
Filled hole with mud to 35'.
Set 2nd plug at 35' w/10 sx.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Musgrove Petroleum Corporation,
Address 518 Petroleum Building, Wichita, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK
I, GORDON L. KOELLING, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gordon L. Koelling
518 Petroleum Bldg., Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of September, 19 54

My commission expires July 16, 1955 _____
Notary Public.

PLUGGING
FILE SEC 1 T 29 R 14
BOOK PAGE 61 LINE 33

STATE CORPORATION COMMISSION
Wichita, Kansas

09-14-54

CONTRACTOR'S WELL LOG

COMPANY: R. L. Ferguson & Musgrove Petroleum Corporation
 CONTRACTOR: Musgrove Petroleum Corporation
 FARM: MOORE A #1
 LOCATION: SE SW SE (W/2 SE/4)
 Sec. 1-29-14, Pratt County, Ks.
 COMMENCED: August 20, 1954
 COMPLETED: September 5, 1954

0	103	Surface soil
103	228	Sand
228	807	Red bed
807	830	Anhydrite
830	1435	Shale & red bed
1435	1795	Shale & lime
1795	2110	Shale & shells
2110	3975	Shale & lime
3975	4032	Shale, lime, sand
4032	4130	Lime
4130	4241	Lime & shale
4241	4528	Lime
4528	4576	Lime & chert
4576	4609	Lime
4609	4670	Lime & shale
4670	4705	Arbuckle
	4705	Rotary Total Depth

Set 8-5/8" surface at 338" with 200 sacks of cement, 2% calcium chloride.
 Dry & Abandoned.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, GORDON L. KOELLING, do hereby certify that the above and foregoing is a true and correct copy of the log of the MOORE A #1, SE SW SE Section 1-29-14 West, Pratt County, Kansas as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION

By Gordon L. Koelling
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 9th day of September, 1954.

Wm. E. Raab
 Notary Public

My commission expires July 16, 1955.

PLUGGING
 FILE SEC-1-29-14
 BOOK PAGE 61 LINE 33

RECEIVED