

15151-00247-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD

PRATT County, Sec. 36 Twp. 29 Rge. 13 (E) (W)

Location as "NE/CNWxSWx" or footage from lines SW SW NE

Lease Owner TIME PETROLEUM COMPANY

Lease Name OSBORNE Well No. 1

Office Address 512 ORPHEUM BUILDING WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed 11-20 19 55

Application for plugging filed 11-20 19 55

Application for plugging approved 11-20 19 55

Plugging commenced 11-20 19 55

Plugging completed 11-20 19 55

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well M. A. RIVES

Producing formation Depth to top Bottom Total Depth of Well 4745 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 394' | NONE |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 350 FEET.

SET FIRST PLUG WITH 20 SACKS CEMENT.

FILLED HOLE WITH HEAVY MUD TO 40 FEET.

SET SECOND PLUG WITH 10 SACKS CEMENT.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES DRILLING COMPANY

Address 514 ORPHEUM BUILDING WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

R. R. GREENBAUM

(owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)


512 ORPHEUM BUILDING, WICHITA

(Address)

SUBSCRIBED AND SWORN to before me this 28 day of NOVEMBER, 19 55

My commission expires 11-19-58

Notary Public.



GABBERT-JONES DRILLING COMPANY
WICHITA, KANSAS
DRILLERS WELL LOG

OSBORNE #1
 SW SW NE SECTION 36-29-13W
 PRATT COUNTY, KANSAS
 COMMENCED 10-29-55
 COMPLETED 11-20-55

| DEPTH | | FORMATION | REMARKS |
|-------|------|-----------------------|---|
| FROM | TO | | |
| 0 | 155 | SURFACE CLAY AND SAND | |
| 155 | 330 | RED BED | |
| 330 | 394 | RED BED & SHELLS | RAN 394' OF 8 5/8" CASING CEMENTED W/250 SACKS CEMENT |
| 394 | 1050 | RED BED & SHALE | |
| 1050 | 1620 | SHALE & SHELLS | |
| 1620 | 1880 | SHALE & LIME | |
| 1880 | 1935 | LIME W/SHALE STREAKS | |
| 1935 | 2375 | LIME | |
| 2375 | 2565 | LIME & SHALE | |
| 2565 | 2665 | LIME | |
| 2665 | 3145 | LIME & SHALE | |
| 3145 | 3780 | LIME | |
| 3780 | 3950 | LIME & SHALE | |
| 3950 | 4425 | LIME | |
| 4425 | 4504 | SHALE & LIME | |
| 4504 | 4511 | LIME | |
| 4511 | 4541 | LIME & SHALE | |
| 4541 | 4575 | LIME | |
| 4575 | 4589 | CHERTY LIME | |
| 4589 | 4645 | LIME | |
| 4645 | 4669 | SANDY SHALE | |
| 4669 | 4688 | SHALE | |
| 4688 | 4720 | LIME & SHALE | |
| 4720 | 4745 | ARBUCKLE DOLOMITE | |
| 4745 | TD | | DRY & ABANDONED |

I, E. E. Hall, CERTIFY THIS TO BE A TRUE AND CORRECT COPY OF THE DRILLER'S WELL LOG OF THE OSBORNE #1.

E. E. Hall

STATE OF KANSAS)
 COUNTY OF SEDGWICK)

SS

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC, WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 28th DAY OF November, 1955 PERSONALLY APPEARED E. E. Hall TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET ME HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES 10/29/56

Barbara Oldfield
 NOTARY PUBLIC

PLUGGING
 FILE SEC 36 T 29 R 13 W
 BOOK PAGE 18 LINE 44