

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 22 Twp. 10 Rge. 18 (E) (W)

Location as "NE/CNW\*SW\*" or footage from lines NW NW SE

Lease Owner Lee Phillips, Jr.

Lease Name Shepard Well No. 1

Office Address 1407 Union National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 30, 1955 19

Application for plugging filed May 30, 1955 19

Application for plugging approved May 30, 1955 19


Plugging commenced May 30, 1955 19

Plugging completed May 30, 1955 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3731 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Pipe	0	216'	10-3/4"	216'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 210'.  
Bridged hole at 210'. Ran 20 sacks  
cement 210' up. Bridge hole at 40',  
ran 10 sacks cement, plug 40' to  
base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 3 - 1955 6-3-55  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Isern Drilling Company  
Address Ellinwood, Kansas

STATE OF KANSAS COUNTY OF BARTON  
I. M. M. Shropshire (employee of owner) or owner or operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) I. M. M. Shropshire  
Lyons, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 31st day of May, 1955  
George A. Meyer Notary Public.

My commission expires Feb. 10, 1959

PLUGGING  
FILED SEC 22-10 D 18W  
BOOK PAGE 124 LINE 1

WELL LOG

LEE PHILLIPS, JR., Owner - Shepard #1  
NW/4 NW/4 SE/4 Section 22, Township 10, Range 18W,  
Rooks County, Kansas

ELEVATION: 2064 DF

Figures indicate bottom of formation  
0 to

15 sand  
40 lime & shale  
70 shale  
224 shale & shells  
730 shells & shale  
840 sand  
900 shells & shale  
1130 sand  
1140 shale & shells  
1150 Anhydrite  
1800 shale & shells  
1915 salt  
2150 shale & shells  
2365 lime & shale  
2555 shale & shells  
2795 lime & shale  
2835 shale & shells  
3235 lime & shale  
3551 lime  
3634 Conglomerate  
3690 shale  
3731 Arbuckle  
3731 Total Rotary  
Depth D&A

PIPE RECORD:

10-3/4" set at 216'  
Cemented with 225 sacks.

TOPS: RBM

Heebner 3258  
Toronto 3276  
Kansas City 3301  
Conglomerate 3551  
Simpson 3668  
Arbuckle 3681

Rotary Commenced 5-21-55  
Completed 5-30-55

STATE OF KANSAS )  
COUNTY OF BARTON ) SS

I, M. M. Shropshire, Drilling Superintendent of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above described well, as filed, and that the same are true and correct.

RECEIVED  
STATE CORPORATION COMMISSION

JUNE - 1955

CONSERVATION DIVISION

Subscribed and Sworn to before me this 31st day of May, 1955.

M. M. Shropshire

George A. Meyer  
Notary Public

My commission expires Feb. 10, 1959.

PLUGGING  
RM SEC 22-10-R-18W  
BOOK PAGE 124 LINE 1