


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Flat

Sedgwick County. Sec. 32 Twp. 27 Rge. 4 (E) X (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW/c SW/4
Lease Owner Dunne & Strait Drilling Company
Lease Name Silas Brown Well No. 1
Office Address 300 Schweiter Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 10 19 50
Application for plugging filed May 10 19 50
Application for plugging approved May 10 19 50
Plugging commenced May 10 19 50
Plugging completed May 10 19 50
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 10
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well D. C. Lilley, 800 Bitting Bldg., Wichita, Ks
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with rotary mud within 200 feet of top or to bottom of surface pipe.
Set bridge with wooden plug and cemented with 12 sax cement. Pumped heavy rotary mud on top of cement to 6 ft. of base of cellar. Bridged with wooden plug and cemented with 3 sax cement to top of surface pipe or base of cellar, for cap plug.

RECEIVED

Cons. Div.

MAY 16 1950 5-16-50

STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Dunne & Strait Drilling Company
Address 300 Schweiter Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

D. E. Dunne, Jr. (employee or owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


DUNNE & STRAIT DRILLING COMPANY
By [Signature]
(Signature)

300 Schweiter Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of May, 1950
[Signature]

Notary Public.

My commission expires May 25, 1952



WELL LOG - Silas Brown Well #1

OPERATOR: Dunne & Strait Drilling Company
300 Schweiter Building
Wichita, Kansas

LOCATION: NW/c SW/4
Section 32, Township 27,
Range 4 West, Sedgwick County,
Kansas

CONTRACTOR: Morrison Drilling Company, Inc.
P. O. Drawer 712
El Dorado, Kansas

PRODUCTION _____

Farm: Silas Brown Well No. 1

Date Commenced: April 26, 1950

Date Completed: May 10, 1950

Total Depth: 3807 Feet

<u>From</u>	<u>To</u>	<u>Formation</u>
0	10	Red Bed
10	75	Red Clay and Sand
75	200	Surface sand
200	710	Shale & Shells
710	1000	Shale & Lime Strks.
1000	1210	Shale & Lime
1210	1500	Lime & Shale Brks.
1500	1560	Shale & Lime Strks.
1560	2125	Shale & Shells
2125	2280	Shale & Lime Strks.
2280	2609	Lime & Shale
2609	2628	Shale
2628	2894	Lime & Shale
2894	2904	Lime & Shale Strks.
2904	3174	Lime
3174	3230	Lime & Shale Brks.
3230	3365	Lime
3365	3377	Shale & Lime Brks.
3377	3512	Lime & Shale
3512	3550	Lime & Shale Brks.
3550	3579	Lime & Shale
3579	3606	Shale & Lime Strks.
3606	3700	Shale & Lime
3700	3729	Shale
3729	3761	Shale & Lime
3761	3807	Lime
3807		Total Depth

RECEIVED
MAY 16 1950
STATE CORPORATION
COMMISSION
KANSAS

I hereby certify that the foregoing is a true and correct copy of the Well Log for the Silas Brown Well No. 1 drilled for Dunne & Strait Drilling Company and completed May 10, 1950.

(Sgd.) C. W. Wilson
C. W. Wilson
Secretary-Treasurer

PLUGGING
FILE SEC 32 T 27 R 4 W
BOOK PAGE 5 LINE 8