

STATE OF KANSAS
CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Pratt County, Sec. 19 Twp. 27 Rge. 12 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW
Lease Owner Clay Newell
Lease Name Seidel Well No. 1
Office Address Box "D" Stafford, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9/11 1971
Plugging completed 9/21/71 1971
Reason for abandonment of well or producing formation _____

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Russell Beberstein
Producing formation Simpson Depth to top _____ Bottom _____ Total Depth of Well 4353 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	357'	0
				5 1/2"	4326'	2349'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Filled with sand from 4353' to 4300'. Set plug at 270'. Rock to 260'.
Run 4 yards of ready mix cement from 260' to base of cellar.


RECEIVED
STATE CORPORATION COMMISSION
OCT 12 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.
Address Box 156 Ellinwood, Kansas 67526

STATE OF Kansas, COUNTY OF Stafford, ss.
Clay H. Newell (~~employee of owner~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clay Newell
Stafford, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 11th day of October, 1971



G. Titus Hawver
(G. Titus Hawver) Notary Public.

Seidel #1
NE NE NW
Sec. 19-27S-12W
Pratt County, Kansas

Started 12/9/52
Completed 12/30/52

Driller: Schaffer Drilling Co.

LOG

0 to 90'	-	Surface clay & sand
90 to 129'	-	Shale & sand
129 to 190'	-	Shale
190 to 220'	-	Shale & shells
220 to 665'	-	Red Bed
665 to 710'	-	Anhydrite
710 to 790'	-	Red Bed
790 to 1230'	-	Red Bed, Shale & shells
1230 to 1820'	-	Shale & shells
1820 to 1835'	-	Lime & shale
1885 to 2115'	-	Lime
2115 to 2495'	-	Lime & shale
2495 to 2640'	-	Shale
2640 to 3315'	-	Shale & lime
3315 to 3522'	-	Lime
3522 to 3695'	-	Lime & shale
3695 to 3730'	-	Lime
3730 to 3765'	-	Lime & shale
3765 to 4159'	-	Lime
4159 to 4195'	-	Chert & shale
4195 to 4270'	-	Lime & shale
4270 to 4285'	-	Coring
4285 to 4307'	-	Sand
4307 to 4315'	-	Sand & shale
4315 to 4326'	-	Sand
4326 to 4329'	-	Shale
4329 to 4340'	-	Sand & shale
4340 to 4345'	-	Shale
4345 to 4353'	-	T. D.

RECEIVED
STATE CORPORATION COMMISSION
SEP 9 1971
CONSERVATION DIVISION
Wichita, Kansas