

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 19-9LOCATION SW-SW-SWSEC. 19 TWP. 15 RGE. 13-10Dry Hole Abandoned Oil Well X Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 1 Lease McCandlessOperator Sun Oil Co. Address Box #1348 Tulsa OklaField County StaffordTotal Depth 4336 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/8 - 8345 - Circulated with cement.
5 1/2" casing set at 4001 ft. Plugged back to 4000 ft with
Mud & Plug - Cement from 4000 ft to 3955 ft - Chat &
Sand from 3955 ft to 3850 ft. Dumped 6 sacks of cement
at 3850 ft - Shot off & pulled the 5 1/2" casing - Mud to 850 ft.
Halliburton Pumped in Plug & 400 sacks of cement
filling hole from 850 ft to the surface with cement.
Pipe Pulling, Inc. Plugging Contractors.

Conservation-Div.

AUG 14 1950

8-14-50

STATE CORPORATION

District Conservation Agent

KANSAS

Date

8-11-50

