

KANSAS

99

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 15 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Texaco Inc

Complete Address Box 2420 Tulsa, OK

Lease Name L. Goodman Well No. 3

Location SW/NE/NW Sec. 30 Twp. 25 Rge. 13 (E) (W) W

County Stafford Total Depth 4350

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co. Inc

Address Box 405 Chase, KS License No. 436

Operation Completed: Hour 1:00 PM Day 13 Month 12 Year 1972

The above well was plugged as follows:

320 ft 10 3/4 surface pipe cement circulated. 3970 ft 5 1/2 long string

cemented with 250 sacks. Top perf. 3860 ft. Push plug to 3800 ft.

Sand & 5 sacks cement with bailer. Pulled 2830 ft 5 1/2. Pump 3 sacks

hulls, 20 sacks gel., 150 sacks cement to surface.

Pumped by Halliburton Cementing Co. Great Bend, KS

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *D. Russell B. Bickert*
Well Plugging Supervisor

DATE 12/15/72

INV. NO. 6728-11