

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 31 1978  
CONSERVATION DIVISION  
Wichita, Kansas

8-31-78

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - - of this well)

Operator's Full Name J. E. Delgado et al.

Complete Address 316 Union Center Bldg, Wichita, KS 67202

Lease Name Mc. Cordless "B" Well No. 1

Location NE-NW-NE Sec 30 Twp 23 Rge. 13 (E) (W) X

County Stafford Total Depth 4365

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Nicholas Casing Pulling

Address Box 373, Geneseo, Kans. 67444 License No. 711

Operation Completed: Hour 4:45 pm Day 29 Month 8 Year 1978

The above well was plugged as follows:

342'-8 5/8" Casing w/ 200 sac Cement - 5 1/2" Casing set @ 4364'  
Top Prefrat. 3865' sand back to 3515' Top sand w/ 5  
sac mixed Cement w/ dump bails. Pull 2502' 5 1/2"  
Casing, mix & pump 5 sac hulls - 25 sac Gel. release  
plug. mix & pump 100 sac 50/50 porous Cement w/  
37 cc. to top of Casing - shut in w/ 350# pressure.  
Supervised By  
Howell Pratt, Jr. 67530

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 8-31-78

INV. NO. 7978-u