

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-185-20692-0000 (of this well)

*R*

Operator's Full Name F & M. Oil Co., Inc.

Complete Address 505 Union Center, Wichita, Ks. 67202

Lease Name Dudrey Well No. 1

Location S/2 SW NE Sec. 27 Twp. 25S Rge. 13 (E) (W) X

County Stafford Total Depth 4326

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling.

Address Box 176-Chase, Ks. 67524 License No. 683

Operation Completed: Hour 10:30 Am. Day 8 Month 10 Year 1979

The above well was plugged as follows:

250' 8 5/8" casing w/225 sax cement. 4 1/2" casing set at 4300' w/150  
sax cement. Sand back to 4250!-Top sand w/4 sax mixed cement w/dump  
bailer-Pull 3630" 4 1/2" casing-Allied mixed & pumped in 8 5/8" casing  
8 sax hulls-25 sax gel-125 sax 50/50 posmix cement w/4% gel & 3% cc  
to top of casing. Shut in w/300# pressure.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 23 1979

CONSERVATION DIVISION  
WICHITA, KANSAS

10-23-79

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: *[Signature]*  
Well Plugging Supervisor

DATE 10-24-79  
INV. NO. 0746-10