

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORTRECEIVED
STATE CORPORATION COMMISSION

MAR 22 1963

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasCONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Aylward Drilling Co.

Complete Address: 813 First Nat'l. Bnk. Bldg. Wichita, Kansas

Lease Name Bowker "B" #1 Well No. #1

Location SW-SE-NE Sec. 7 Twp. 25 Rge. 14 (E) (W) X

County Stafford Total Depth 4213'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Kent Well Service

Address: 2375 West Central Eldorado, Kansas License No. 417

Operation Completed: Hour PM Day 17 Month March Year 1963

The Above well was plugged as follows:

4157' of long string (4 1/2"). Top perforation at 4046' Sanded to 4030' &
3 sacks cement. 226' of 8 5/8" surface pipe circulated with cement.
Hole filled to 200' with mud, 10' rock bridge and 25 sacks cement.
Hole filled to 40' with mud, 10' rock bridge and 10 sacks cement to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 3/22/68INV. NO. 6964-WSigned: Herman Justus

Well Plugging Supervisor