

**KANSAS**  
**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
**STATE CORPORATION COMMISSION**  
**JUN 7 1967**  
**CONSERVATION DIVISION**  
**Wichita, Kansas**

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued May 16, 1967.

Operator's Full Name Frank J. Black

Complete Address: Box 150, McPherson, Kansas 67460

Lease Name Hattie "B" Well No. # 3

Location SE NE SW Sec. 2 Twp. 25 Rge. 14 (E) (W) W

County Stafford Total Depth 4280'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 12:30PM Day 6th Month June Year 1967

The Above well was plugged as follows:

874' of 8 5/8" surface pipe, cement circulated, 4305' of 5 1/2" long string,  
cemented with 200 sacks. Plug back T.D. 4148'. Top perferation 3930'. Bottom  
of the hole was sanded to 3900', and cemented with 5 sacks, through the dump  
bailer. 2818' of 5 1/2" long string was recovered from the hole. Hole was filled  
with mud to 400', rock bridge from 400' to 390', and cemented with 25 sacks.  
Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented  
with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 6/9/67  
INV. NO. 5348-U

Signed: Audie Eving  
Well Plugging Supervisor