

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-155-20,583 (of this well)

Operator's Full Name Eagle Petroleum Company

Complete Address 1400 Douglas Bldg., Wichita, Kansas

Lease Name Saylor Well No. 1

Location C SW NW Sec. 18 Twp. 26 Rge. 8 (E) (W) X

County Reno Total Depth 2600'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor B&N Drilling Co. and Allied Cementing Co.

Address Box 846, Independence, Kansas License No.     

Operation Completed: Hour 4 PM Day 5 Month March Year 1979

The above well was plugged as follows: 8 5/8" - 197' cement circulated  
Hole Filled with mud. 40 sacks cement pumped through drill  
pipe at 500'. 25 sacks cement pumped through drill pipe  
at 195'. Plug and 1/2 sack hulk pushed to 40' and hole  
cemented to base of cellar with 10 sacks cement.  
Rathole bridged and cemented with 2 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
3-8-79  
MAR - 8 1979

I hereby certify that the above well was plugged as herein stated

INVOICED

Signed: [Signature]  
Well Plugging Supervisor  
CONSERVATION DIVISION  
Wichita, Kansas

DATE 3-9-79  
INV. NO. 9235-W