

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-185-21,915-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Kelso Casing Pulling, Inc. KCC LICENSE # 6050
(owner/company name) (operator's)

ADDRESS P.O. Box 347 CITY Chase

STATE Kansas ZIP CODE 67524 CONTACT PHONE # (316) 938-2943

LEASE Garner "A" WELL# 1 SEC. 20 T. 25 R. 13W (East/West)

NW - SW - NW - SPOT LOCATION/QQQQ COUNTY Stafford

_____ FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

_____ FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL _____ D&A _____ SWD/ENHR WELL _____ DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 374' CEMENTED WITH 275' SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 4362' CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4264'-4283'

ELEVATION 1951/ 1961 T.D. 4363' PBSD _____ ANHYDRITE DEPTH 837'-1124'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING We will plug the well according to the rules and regulations of the State of Kansas.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? Scout card copy

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Kelso Casing Pulling, Inc. PHONE# (316) 938-2943

ADDRESS P.O. Box 347 City/State Chase, Kansas 67524

PLUGGING CONTRACTOR Kelso Casing Pulling, Inc. KCC LICENSE # 6050
(company name) (contractor)

ADDRESS P.O. Box 347 Chase, KS 67524-0347 PHONE # (316) 938-2943

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) ASAP

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR/AGENT

DATE: 7-15-93 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)

RECEIVED
CONSERVATION DIVISION
JUL 16 1993
STATE CORPORATION COMMISSION
KANSAS

11

BROUGHER OIL, INC.

P. O. DRAWER 1367

#1 "A" GARNER

20-25-13W

NW SW NW


GREAT BEND, KS 67530

CONTR MOHAWK DRILLING, INC.

CTY STAFFORD

GEOL

FIELD KACHELMAN



ELV 1961 KB SPD 1/25/84 CARD ISSUED 3/15/84 IP P 75 BO & 110 BWPD
1951 GL SIMP SD 4264-4283 OA

LOG	Tops	Depth/Datum
ANH	837+1124
HEEB	3544-1583
TOR	3564-1603
DOUG	3582-1621
BR LM	3699-1738
LANS	3728-1767
BKC	4009-2048
CONG CHT	4071-2110
MISS	4129-2168
MIND	4148-2187
VIOLA	4211-2250
1ST SIMP SD	4263-2302
2ND SIMP SD	4277-2316
ARB	4325-2364
LTD	4362-2401

API 15-185-21,915

8 5/8 " 374 / 275SX; 5 1/2 " 4362 / 150SX

DST (1) 4097-4150 (MISS) / 45-45-45-45, WB, REC 50' M, SIP 119-169#, FP 50-99 / 99-119#, HP 2287-2287#

DST (2) 4204-4251 (VIOLA) / 45-45-45-45, FB, 64' GIP, REC 192' THIN GCM, SIP 976-898#, FP 39-89 / 89-138#

DST (3) 4252-4291 (2ND SIMP SD) / 45-45-45-45, WB TO GE, 256' GIP, REC 256' SO & GCM, SIP 545-406#, FP 39-99 / 99-148#, HP 2306-2287#

MICT - CO, PF (SIMP SD) 4264-4270, W / 3 SPF, AC 500G (15% FE), SWB DWN, SO, RE-AC 250G (DF) & 2G (HI-FLO), SWB DWN, SO, PF (SIMP SD) 4277-4283, W / 3 SPF, FRAC 30,000# SD & FL (AMT NA), SWB DWN, SO, POP, P 75 BO & 110 BWPD, 2/23/84

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

July 16, 1993

Kelso Casing Pulling Inc

P O Box 347
Chase KS 67524

Garner "A" #1
API 15-185-21,915
NW SW NW
Sec. 20-25S-13W
Stafford County

Dear Kelso Casing Pulling Inc,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #1 304 W. McArtor
Dodge City KS 67801
(316) 225-6760