

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-185-21,992-0006 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Kelso Casing Pulling, Inc. KCC LICENSE # 6050
ADDRESS P.O. Box 347 (owner/company name) CITY Chase (operator's)

STATE Kansas ZIP CODE 67524 CONTACT PHONE # (316) 938-2943

LEASE Garner "A" WELL# 2 SEC. 20 T. 25 R. 13W (East/West)

NW - NW - NW - SPOT LOCATION/QQQQ COUNTY Stafford

FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL DGA SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 424' CEMENTED WITH 300 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 4354' CEMENTED WITH 300 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4258'-68'

ELEVATION 1953 / 1963 T.D. 4355' PSTD _____ ANHYDRITE DEPTH 836'-1127'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING We will plug the well according to the rules and regulations of the State of Kansas.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No scout card

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Kelso Casing Pulling, Inc. PHONE# (316) 938-2943

ADDRESS P.O. Box 347 City/State Chase, Kansas 67524

PLUGGING CONTRACTOR Kelso Casing Pulling, Inc. KCC LICENSE # 6050

ADDRESS P.O. Box 347 Chase, KS 67524 PHONE # (316) 938-2943
(company name) (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) ASAP

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 7-15-93 AUTHORIZED OPERATOR/AGENT: [Signature]
(signature)

RECEIVED
JUL 16 1993
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

BROUGHER OIL, INC.
P. O. DRAWER 1367

#2 "A" GARNER

20-25-13W
NW NW NW

GREAT BEND, KS 67530

CONTR MOHAWK DRILLING, INC. CTY STAFFORD

GEOL BRENT B. REINHARDT FIELD KACHELMAN

0		
+	+	+
+	+	+
+	+	+

ELV 1963 KB SPD 5/31/84 CARD ISSUED 8/16/84 IP P 145 BO & 60 BWPD
1953 GL SIMP 4258-4268
API 15-185-21,992

LOG	Tops	Depth/Datum
ANH		836+1127
HEEB		3527-1564
TOR		3546-1583
DOUG		3564-1601
BR LM		3681-1718
LANS		3712-1749
BKC		3990-2027
CONG		4043-2080
MISS		4073-2110
KIND		4088-2125
VIOLA		4135-2172
SIMP SH		4252-2289
1ST SIMP SD		4256-2293
2ND SIMP SD		4274-2311
ARB		4315-2352

8 5/8 " 424/300SX, 5 1/2 " 4354/300SX

DST (1) 3760-3819 (LKC E-G) / 45-60-60-60, 90' GIP, REC 30'
GSY DM, 300' GSY M, W/OIL SPKS, 120' FROTHY G&OCM, 150'
HO&GCM, 150' GSY MCW, SIP 1246-1225#, FP 307-307 / 328-
349#

DST (2) 3940-60 (LKC K) / 45-45-30-45, REC 160' M, W/FEW
OIL SPKS, SIP 1109-1014#, FP 63-63 / 74-74#, HP 2260-
2207#, BHT 118°

DST (3) 4040-4105 (CONG, MISS) / 45-45-45-45, REC 90' GSY
M, SIP 317-296#, FP 84-84 / 84-84#, HP 2260-2207#, BHT
118°

DST (4) 4230-90 (SIMP) / TIMES NA, REC 90' SO&GCM, 120'
HO&GCM, 480' GSY MCO, SIP 444-444#, FP 254-296 / 307-
338#, HP 2377-2366#, BHT 120°

MICT - CO, PF (SIMP) 4258-68 W/3 SPF, AC 1500G (15% MCA),
FRAC 10,000# SD & FL, SWB DWN, SO, SET 2 7/8 " TBG AT
4335', POP, P 145 BO & 60 BWPD, 7/5/84

RTD 4355-2392

LTD 4356-2393

COPYRIGHT 1984
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

July 16, 1993

Kelso Casing Pulling Inc
P O Box 347
Chase KS 67524

Garner "A" #2
API 15-185-21,992
NW NW NW
Sec. 20-25S-13W
Stafford County

Dear Kelso Casing Pulling Inc

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script, appearing to read "David P. Williams".

David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1236
Telephone (316) 263-3238

District: #1 304 W. McArtor
Dodge City KS 67801
(316) 225-6760