


STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
P. O. BOX 17027
WICHITA, KANSAS 67217

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Stafford County, Sec. 20 Twp. 25 Rge. 13 (E) (WXX)
Location as "NE/CNW&SW" or footage from lines SW/NE/NW
Lease Owner Woodman-Tannitti Drilling Co.
Lease Name GARNER Well No. 1
Office Address P. O. Box 308, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced October 20, 1975
Plugging completed October 30, 1975
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation Depth to top Bottom Total Depth of Well 4389 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	321	-0-
				5 1/2	4380	3716.90'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged bottom back to 4000' with sand and 5 sacks cement.
Shot casing at 3710'. Spotted oil. Pulled a total of 118 joints of 5 1/2" casing. Plugged well with 3 sacks hulls, 10 sacks gel and 100 sacks 50/50 Pozmix.


RECEIVED
CONSERVATION DIVISION
11-4-75
4 1975

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Rockhold Engineering, Inc.
Address P. O. Box 698, Great Bend, Kansas 67530

CONSERVATION DIVISION
Wichita, Kansas

STATE OF Kansas COUNTY OF Barton ss.
James W. Rockhold

(employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) James W. Rockhold
Box 698, Great Bend, Kansas 67530
(Address)

day of November 1975

My commission expires September 30, 1979

Cathy Peacock Notary Public.

K. T. WOODMAN
RES. PHONE 733-0418
OFF. PHONE 265-7650
WICHITA, KANSAS

D. J. IANNITTI
PHONE 792-2921
GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors

1008 UNION NATIONAL BUILDING
WICHITA, KANSAS 67202

October 15, 1975

Company;	Woodman & Iannitti Drilling Co.
Farm;	#1 Garner
Location	SW NE NW
Section;	20-25-13W
County;	Stafford
Contractor;	Woodman & Iannitti Drilling Co.
Comm;	April 26, 1974
Compl;	May 8, 1974
Total Depth;	4390
Casing;	8 5/8" @ 321 w/175 sx. 5 1/2" @ 4280 w/75 sx.

Figures Indicate Bottom Of Formations:

70	Sand
80	Shale
200	Sand
250	Shale
321	Red Bed
600	Red Bed & Shale
750	Sand
835	Red Bed
870	Anhy
980	Shale
1760	Shale
1950	Lime
2510	Lime
3090	Lime & Shale
3430	Lime & Shale
3515	Lime & Shale
3915	Lime
4115	Lime
4215	Lime
4312	Lime
4355	Lime
4390	Lime & Arbuckle

RECEIVED
STATE CORPORATION COMMISSION

OCT 16 1975

CONSERVATION DIVISION
Wichita, Kansas

I certify the above to be a true and correct copy of the driller's log to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.

K. T. Woodman
K. T. Woodman