

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Stafford SEC. 20 TWP. 25 RGE. 13 E/W  
Location as in quarters or footage from lines:  
SW/NW/NW


Locate Well  
correctly on above  
Section Platt.

Lease Owner Petromark Exploration, Inc.  
 Lease Name Garner Well No. #1  
 Office Address Box 1609 - Great Bend, Ks. 67530  
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced December 24, 1982  
 Plugging completed January 4, 1983  
 Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4373'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	418'	NONE
				4 1/2"	4369'	3082.23'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dumped sand to 4040' and four (4) sacks cement.  
Shot pipe @ 3650', 3300' and 3030'.  
Pulled seventy-six (76) joints of 4 1/2" casing.  
Squeezed well with four (4) sacks hulls, fifteen (15) sacks gel,  
fifty (50) sacks cement, fifteen (15) sacks gel, one (1) sack  
hulls. Released plug and pumped one hundred (100) sacks 50/50 pozmix  
cement with 2% added gel and 3% calcium chloride. Max press. 700 psi  
and shut in at 500 lbs. psi. Completed at 11:30 a.m.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.

James W. Rockhold (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold  
 JAMES W. ROCKHOLD Box 698 - Great Bend, Ks.  
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 7<sup>th</sup> day of Jan., 1983



Margaret Prosser  
 Notary Public.  
 JAN 10 1983  
 CONSERVATION DIVISION  
 Wichita, Kansas

My Commission expires: