

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

STAFFORD County. Sec. 20 Twp. 25S Rge. (E) 13 (W)

Location as "NE/CNWxSWx" or footage from lines SE SE NE  
Lease Owner Chief Drilling Co., Inc.  
Lease Name Kipp Well No. 4  
Office Address P. O. Box 797, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) DBA  
Date well completed 5-1-61 19  
Application for plugging filed 5-1-61 19  
Application for plugging approved 5-1-61 19  
Plugging commenced 5-1-61 19  
Plugging completed 5-1-61 19  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot, St. John, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4365 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	269'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set wooden plug and 1/3 sack hulls at 240'.  
Mixed 20 sacks cement through drill pipe.  
1/3 Sack of Hulls, wooden plug set at 35'.  
Mixed 10 sacks cement through drill pipe.

FILED  
STATE CORPORATION COMMISSION

MAY 3 1961

CONSERVATION DIVISION  
Wichita, Kansas

5-3-61

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.  
Address P. O. Box 797, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.  
V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) V. Richard Hoover  
V. Richard Hoover, President  
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of May, 1961

My commission expires October 3, 1964.

Helen E. Fischer  
Helen E. Fischer Notary Public.



WELL LOG

Chief Drilling Co., Inc.  
P. O. Box 797  
Great Bend, Kansas

No. 4 Kipp  
SE SE NE Sec. 20-25S-13W  
Stafford County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 4-18-61  
Completed: 5-1-61

Casing Record: 8-5/8" @ 269' cemented with 175 sacks Sunset Cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Sand	0	230'	1950' Gr.
Clay and Redbed	230'	268'	1952' D.F.
Redbed Shale	268'	515'	1955' K.B.
Sand	515'	625'	
Red Shale	625'	790'	
Shale and Shells	790'	829'	
Anhydrite	829'	845'	
Shale and Shells	845'	1630'	
Shale and Lime	1630'	1800'	
Lime and Shale	1800'	2325'	
Lime	2325'	2425'	
Lime and Shale Streaks	2425'	2585'	
Lime and Shale	2585'	3465'	
Lime	3465'	3536'	
Shale and Lime	3536'	3724'	
Lime	3724'	4005'	
Shale and Lime	4005'	4094'	
Chert	4094'	4126'	
Shale and Chert	4126'	4216'	
Chert	4216'	4300'	
Lime and Chert	4300'	4318'	
Shale	4318'	4323'	
Sand	4323'	4349'	
Shale	4349'	4365'	
Total Depth	4365'		

FORMATION TOPS

Anhydrite	829'	(+1126)
Heebner	3536'	(-1581)
Brown Lime	3693'	(-1738)
Lansing	3724'	(-1769)
Base Kansas City	4005'	(-2050)
Mississippi	4094'	(-2139)
Viola	4216'	(-2216)
Crystalline Viola	4300'	(-2345)
Simpson Shale	4318'	(-2363)
Simpson Sand	4323'	(-2368)
Total Depth	4365'	(-2410)

RECEIVED  
STATE CONSERVATION COMMISSION

3 1961  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS, COUNTY OF BARTON) SS.

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the SE SE NE Sec. 20-25S-13W, Stafford County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

*V. Richard Hoover*  
V. Richard Hoover, President

Subscribed and sworn to before me this 2nd day of May, 1961.

My commission expires: October 3, 1964.

*Helen E. Fischer*  
Helen E. Fischer, Notary Public