

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-185-21,915-0000

LEASE NAME Garner "A"

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 20 TWP. 25 RGE. 13W(E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 7-20-93

Plugging Completed 8-2-93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Kelso casing Pulling, Inc.

ADDRESS P. O. Box 347, Chase, KS 67524

PHONE# (316) 938-2943 OPERATORS LICENSE NO. 6050

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 4363'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	374'	none
				5 1/2"	4362'	2700'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged off bottom with sand & 5 sks cement @ 4200'. Shot at 3410', 3220', 3000', 2810'
& 2700'. Pulled pipe. Plugged well with 300# hulls, 10 sks gel, 50 sks cement, 10 sks gel,
100# hulls, plug, & 100 sks cement. Plugging complete. 60/40 pos 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kelso Casing Pulling, Inc. **AUG 16 1993**

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 13th day of August, 19 93

Irene Herzberg
 Notary Public

My Commission Expires:

