


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 21 Twp. 25 Rge. 13W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW SW NW
Lease Owner Bennett & Roberts Oil Operations
Lease Name McCandless Well No. 1
Office Address Russell, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10/27 19 60
Application for plugging filed 10/27 verbally 19 60
Application for plugging approved 10/27 verbally 19 60
Plugging commenced 10/27 19 60
Plugging completed 10/27 19 60
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4398 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	334'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud back to 320' - 1/4 sx hulls - plug - 25 sx cement - mud to 40'

1/2 sx hulls - plug - 10 sx cement - 2 sx in rat hole.

RECEIVED
STATE CORPORATION COMMISSION

NOV 2 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____
Address _____

STATE OF KANSAS, COUNTY OF RUSSELL, ss.
Harold Wurst (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Wurst
Russell, Ks.
(Address)

SUBSCRIBED AND SWORN to before me this 1st day of November, 19 60

Clara Hummel
Notary Public.

My commission expires 6/17/62

Bennett & Roberts Oil Operations
MC CANDLESS #1

NW SW NW Sec. 21-25-13W
Stafford County, Kansas

RTD 4398

CONTRACTOR: Bennett & Roberts Drilling, Inc.

Commenced 10/11/60
Completed 10/27/60

Set 334' of 8 5/8" w/275 sx

Sand	185'
Red Bed	220
Red Bed & Shells	333
Red Bed & Shale	550
Red Bed, Shale & Shells	1000
Shale & Shells	1675
Shale & Lime	1940
Lime	2404
Lime & Shale	2780
Shale, Lime & Shells	2943
Lime & Shale	3398
Lime	3564
Lime & Shale	3771
Lime	4197
Chert & Lime	4291
Sand & Shale	4313
Lime & Shale	4350
Lime	4398

STATE OF KANSAS)

RUSSELL COUNTY.) SS.

STATE OF KANSAS
COMMISSIONER

NOV 12 1960

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above information is correct to the best of my knowledge.

BENNETT & ROBERTS DRILLING, INC.

By Janice Lee Marshall

Subscribed and sworn to before me this 1st day of November, 1960.

Clara L. Hummer
Notary Public

My Commission Expires 6/17/62

