

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Stafford County. Sec. 17 Twp. 25 Rge. 13 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW/4

Lease Owner Musgrove Drilling Company

Lease Name Lyons #1 Well No.

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 4-22-60 19

Plugging completed 4-25-60 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation Depth to top Bottom Total Depth of Well 4280 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	300'	none
				5-1/2"	4271'	3336'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole to 4280' and found it open.
Filled w/sand to 4265' and dumped 5 sacks of
cement with bailer. Pulled 5 1/2" casing.
Cleared hole and bailed hole to 200', set
rock bridge to 190', and dumped 20 sacks of
cement. Mudded the hole to 40', set rock
bridge to 30' and ran 10 sacks of cement to
base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETED

APR 28 1960

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Knight Casing Pulling Co.

Address Chase, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
I, Noell J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 26th day of April, 19 60.

My commission expires 9-27-62 Notary Public.

CONTRACTOR'S WELL LOG

COMPANY:	Musgrove Petroleum Corporation
CONTRACTOR:	Musgrove Petroleum Corporation
FARM:	LYONS #1
LOCATION:	NE SW NW Sec. 17-25-13W Stafford County, Kansas
COMMENCED:	March 21, 1958
COMPLETED:	April 5, 1958

0	130	Topsoil & sand
130	1789	Shale & shells
1789	2100	Lime & shale
2100	2435	Lime, shale & shells
2435	2780	Lime & shale
2780	2960	Lime, shells & shale
2960	3360	Lime & shale
3360	3445	Lime
3445	3750	Lime & shale
3750	3855	Lime
3855	3880	Lime & shale
3880	3950	Lime
3950	3970	Lime & shale
3970	4035	Lime
4035	4045	Chert & lime
4045	4105	Lime & shale
4105	4130	Viola
4130	4155	Lime & shale
4155	4175	Lime
4175	4225	Lime & chert
4225	4235	Lime, shale & chert
4235	4280	Lime
	4280	Rotary Total Depth

RECORDED
 STATE OF KANSAS COMMISSION
 APR 7 1960
 CONSERVATION DIVISION
 Wichita, Kansas

ELECTRIC LOG TOPS:		ELEVATION:	1951° Gr.
Heebner	3510° (-1554)		1954° D.F.
Lansing	3678° (-1722)		1956° K.B.
Base Kansas City	3962° (-2006)		
Mississippi	4015° (-2059)		
Kinderhook	4042° (-2086)		
Viola	4095° (-2139)		
Simpson	4232° (-2276)		
Artuckle	4270° (-2314)		

Set 8-5/8" surface pipe at 320° with 275 ex BA 5.
 Set 5-1/2" pipe at 4271° w/150 ex cement.

STATE OF KANSAS }
) SS
 COUNTY OF SEDGWICK }

I, Emil E. Dowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the LYONS #1, NE SW NW, Section 17-25-13W, Stafford County, Kansas, as reflected by the files of the Musgrove Petroleum Corporation.

MUSGROVE PETROLEUM CORPORATION
 BY Emil E. Dowers
 Secretary-Treasurer

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 8th day of April, 1958.

Leah Jaye Heffke
 Notary Public

My commission expires June 16, 1959.