


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 17 Twp. 25 Rge. 13 (SE SW NE) (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines SE SW NE
Lease Owner Bankoff Oil Company
Lease Name Garner Well No. 1
Office Address P. O. Box 2479, Tulsa 1, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) D & A.
Date well completed 7-12 19 56
Application for plugging filed 7-12 19 56
Application for plugging approved 7-12 19 56
Plugging commenced 7-12 19 56
Plugging completed 7-12 19 56
Reason for abandonment of well or producing formation D & A.

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well R. M. Brundage, Box 283, Hoisington, Kansas
Producing formation Depth to top Bottom Total Depth of Well 4347 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	304.67	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded to 300'. Added 1/2 sacks of hulls. Set plug
and cemented with 20 sacks of cement. Mudded to
35'. Added 1/2 sacks of hulls. Set plug and cemented
with ten sacks of cement.

Name of Plugging Contractor Welch & Olsson Drilling Company, Inc.
Address 203 Rule Bldg. Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
R.E. Welch (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) [Signature] 203 Rule Bldg. Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16th day of July, 19 56
Edith Erker Notary Public.

My commission expires June 12, 1959

PLUGGING
FILE SEC 17 T 25 R 13W
BOOK PAGE 80 LINE 35

STATE CORP. COM.
JUL 17 1956
CONSERVATION DIVISION
Wichita, Kansas
7-17-56

WELL LOG.

BANKOFF OIL COMPANY,
P. O. Box 2479
Tulsa 1, Okla.

Elevation: 1954 R.B.

Comm. Drlg: 6-29-56

CONTRACTOR: WELCH & OLSSON DRILLING CO. INC.

Compl. Drlg: 7-12-56

GARNER #1
SE SW NE of Sec. 17-25-13W. Stafford
County, Kansas.

Production: D & A.

Casing Record.

Set 304.67' of 8 5/8" with 250 sacks of cement.

(Figures indicated bottom of formations.)

<u>FORMATIONS</u>	<u>DEPTHS.</u>
Sand & Clay:	160
Clay & Shale:	305
Red Bed & Shale:	370
Shale W/sand streaks:	480
Red Bed & Shale:	824
Anhydrite:	841
Shale & Shells:	1675
Shale & Lime Streaks:	1770
Shale & Lime:	3185
Lime & Shale:	3671
Lime:	4040
Lime & Chert:	4080
Lime:	4347 T.D.

STATE OF KANSAS,)
) SS:
SEDGWICK COUNTY,)


I hereby certify that the above is a true and correct copy of Drillers Log of well drilled in the SE SW NE of Section 17, Township 25, Range 13 West, Stafford County, Kansas.

WELCH & OLSSON DRILLING COMPANY, INC.

BY 

R. E. WELCH

Subscribed and sworn to before me this 16th day of July, 1956


Edith Erker, Notary Public.

My commission expires:
June 12, 1959

COMMISSION

JUL 17 1956

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING		
FILE	SEC. 17 T. 25 R. 13W	
BOOK	PAGE 80	LINE 35