


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
217 No. Broadway
Wichita, Kansas 67217

WELL PLUGGING RECORD

Box 17027 Stafford County. Sec. 17 Twp. 25S Rge. 13 (W)
Location as "NE/CNW/SW" or footage from lines SE SW NW



Lease Owner Tomlinson Oil Co., Inc.
Lease Name Lyon Well No. 1
Office Address Suite 1030, 200 W. Douglas, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 16 19 73
Application for plugging filed April 16 19 73
Application for plugging approved April 16 19 73
Plugging commenced April 16 19 73
Plugging completed April 16 19 73
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein, Attica, Kansas 67009
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4317 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	306'	8 5/8"	306'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug: 250' w/40 sacks cement
40' w/15 sacks cement
2 sacks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1973
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hellar Drilling Company, Inc.
Address 339 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
D. L. Hellar, President of Hellar Drlg. Co. Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. L. Hellar D. L. Hellar, President
339 Union Center Bldg., Wichita, Kansas 67202
(Address)

Subscribed and sworn to before me this 25th day of April, 19 73
My commission expires March 25, 1976



Catherine Darcey
Catherine Darcey - Notary Public.

DRILLER'S LOG

COMPANY: Tomlinson Oil Co., Inc., Suite 1030, 200 W. Douglas, Wichita, Kansas 67202
CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas 67202
LEASE: #1 Lyon
LOCATION: SE SW NW 17-25S-13W, Stafford County, Kansas
COMMENCED: April 4, 1973
COMPLETED: April 16, 1973
CASING: Set 8 5/8" Surface Casing @ 306' w/300 sacks cement

0-306 Surface Soil & Lime & Sand
306-837 Red Bed & Shale
837-855 Anhydrite
855-1191 Red Bed & Shale
1191-1640 Red Bed & Shale & Salt
1640-1775 Shale
1775-1845 Shale & Anhydrite
1845-2147 Salt Section
2147-2340 Lime & Shale
2340-2663 Lime-Ft. Riley
2663-2810 Lime
2810-3072 Lime w/Shale Streaks
3072-3145 Lime & Shale
3145-3320 Lime & Shale (Topeka)
3320-3448 Lime & Shale
3448-3670 Lime w/Shale Streaks
3670-3769 Lime & Shale
3769-3911 Lime (L.K.C.)
3911-3962 Lime
3962-4034 Lime w/Shale Streaks & Chert
4034-4127 Lime w/Shale Steaks & Shaley Chert
4127-4208 Conglomerate
4208-4242 Lime
4242-4277 Simpson
4277-4317 Simpson & Arbuckle
4317 Rotary Total Depth

D & A

RECEIVED
STATE CORPORATION COMMISSION
APR 27 1973
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Lyon, located in SE SW NW 17-25S-13W, Stafford County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By [Signature]
President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 25th day of April, 1973.

[Signature]
Notary Public - Catherine Darcey

My Commission Expires:
March 25, 1976

