


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD
OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 18. Twp. 25. Rge. (E) 13 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines Gen. NE 1/4 NE 1/4 NE 1/4
Lease Owner Elbar Corporation
Lease Name Curtis Well No. 1
Office Address 33 South Clark Street, Chicago, Illinois.
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole.
Date, well completed July 30, 1941.
Application for plugging filed July 30, 1941.
Application for plugging approved July 30, 1941.
Plugging Commenced July 30, 1941.
Plugging Completed July 30, 1941.
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 193
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well T. C. Alexander
Producing formation Depth to top Bottom Total Depth of Well 4320 Feet.
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	400'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with mud to 400 feet.
Permanent bridge at 400 feet and cemented with 13 Sx. Cement.
Mud to 38 feet and cement with 12 Sx. cement.
Cement to top.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Beardmore Drilling Company, Inc.
Address 606 Ellis-Singleton Building, Wichita, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Heber Beardmore, Jr. (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God

(Signature) Heber Beardmore, Jr.

606 Ellis-Singleton Bldg., Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of July, 1941.

My commission expires December 6, 1943.

Jane E. Macaulay
Notary Public.

8-1-41

Curtis No. 1 Well

NE/4 NE/4 1E/4 Section 18-25S-13W,
Stafford County, Kansas.

Drilled for: Elbar Corporation
Drilled by: Beardmore Drilling Company, Inc.

Casing Record:

8-5/8" 400'

Drilling Commenced: July 9, 1941.
Drilling Completed: July 30, 1941.

<u>FORMATION</u>	<u>DEPTH</u>
surface	400
red bed, sand & shale	775
red bed & shale	825
sandy lime	845
shale & shells	1400
shale, shells & salt	1700
shale & lime	1845
lime	1980
shale & lime	2340
lime	2390
shale & lime	2455
lime	2540
shale & shells	2610
shale & lime	2880
shale	3035
shale & lime	3060
shale	3110
lime	3150
sandy lime	3250
broken lime	3445
lime	3500
shale & lime	3640
shale	3665
lime	3810
shale & lime	3855
lime	4000
shale	4025
lime	4030
shale	4070
broken lime	4115
lime	4255
shale & lime	4290
lime	4293
cored lime	4303
lime	4320 T.D.

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

EXHIBIT
FILED 18 25 R 13 W
BOOK 149 LINE 18

I, the undersigned, being duly sworn on oath, state that the above and within statement is a true and correct record and log of the well drilled on the location above described, to the best of my knowledge and belief.

Subscribed and sworn to before me this 31st day of July, 1941.

June E. Macaulay
Notary Public

My Commission Expires December 6, 1943.

STATE OF KANSAS
COUNTY OF SEDGWICK