

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford County, Sec. 18 Twp. 25S Rge. 13 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW NE NE
Lease Owner National Cooperative Refinery Association
Lease Name Curtis Well No. 2
Office Address 305 Rule Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 7, 1955
Application for plugging filed March 7, 1955
Application for plugging approved March 8, 1955
Plugging commenced March 7, 1955
Plugging completed March 7, 1955
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4325 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	280'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole and pumped plug with wire line to 270' from top of cellar. Cemented with 90 sacks on up to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAR 11 1955
CONSERVATION DIVISION
Wichita, Kansas

3-11-55

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor M. B. Armer
Address Petroleum Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. R. Sears (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears
305 Rule Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of March, 1955

My commission expires June 30, 1958

C. Orville May Notary Public

PLUGGING
FILE SEC 18 T 25 R 13W
BOOK PAGE 102 LINE 13

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **National Cooperative Refinery Assn.**

SEC. 18 T. 25 R. 13W
 LOC. SW NE NE

FARM **Curtis** NO. 2

TOTAL DEPTH **4325**

COUNTY **Stafford**
 KANSAS


COMM. **2/21/55**

COMP. **3/8/55**

SHOT OR TREATED

CONTRACTOR **M. B. Armer**

ISSUED



CASING

20	10	
15	8	280'
12	6	
13	5	

ELEVATION **1961 K.B.**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	160
Sand & Red Bed	200
Red Bed & Shells	280
Red Bed	430
Sand	510
Red Bed	830
Anhydrite	850
Shale	1045
Shale & Shells	1100
Shale & Lime	1730
Lime	2000
Shale & Lime	2350
Broken Lime	2490
Shale & Lime	3717
Lime	3733
Shale & Lime	3825
Lime	3827
Shale & Lime	3900
Lime	3902
Shale & Lime	4045
Chert	4078
Cherty Lime	4126
Chert	4160
Cherty Lime	4189
Chert & Shale	4217
Cherty Lime	4237
Shale & Lime	4280
Sand & Shale	4285
Shale & Lime	4313
Lime	4325

FORMATION TOPS

HEEBNER	3512
TORONTO	3530
BROWN LIME	3656
LANGING	3682
CONGLOMERATE	4036
MISSISSIPPI	4043
KINDERHOOK	4056
SIMPSON SHALE	4230
SIMPSON SAND	4263
SIMPSON DOLOMITE	4297
ARBUCKLE	4301

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 12 1955
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

M. B. ARMER

By *[Signature]*

STATE OF KANSAS)
) SS:
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a notary public, in and for said County and State this 9th day of March, 1955.

[Signature]

My Commission expires February 13, 1956.

PLUGGING
 FILE SEC 18 T 25 R 13W
 BOOK PAGE 02 LINE 13