


15-185-19175-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

STAFFORD County, Sec. 18 Twp. 25S Rge. 13W (#11) (W)
Location as "NE/CNW/SW" or footage from lines SE NW NW
Lease Owner PETROLEUM, INC.
Lease Name COPELAND "B" Well No. 1
Office Address ROUTE 2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed OCTOBER 23 19 59
Application for plugging filed OCTOBER 23 19 59
Application for plugging approved OCTOBER 23 19 59
Plugging commenced OCTOBER 23 19 59
Plugging completed OCTOBER 23 19 59
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRANK BROADFOOT, 222 SOUTH MAIN, ST. JOHN, KANSAS
Producing formation Depth to top Bottom Total Depth of Well 4331 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	263'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

MUD UP WITH HEAVY MUD TO 240' FOLLOWED BY 1/4 SACK OF HULLS AND A WOODEN PLUG.
PLACED 20 SACKS OF CEMENT THROUGH DRILL PIPE ON TOP OF PLUG. MUD UP TO 35'
FOLLOWED BY 1/4 SACK OF HULLS AND A WOODEN PLUG. FILLED HOLE TO BASE OF WELL
CELLAR WITH 10 SACKS OF CEMENT.

RECEIVED
STATE CORPORATION COMMISSION

NOV 9 1959

CONSERVATION DIVISION

11-9-59

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Searle
ROUTE 2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 6TH day of NOVEMBER, 19 59

My commission expires APRIL 14, 1963

Arthur Janice
Notary Public.



WELL LOG

COMPANY PETROLEUM, INCORPORATED

SEC. 18 T. 25S R. 13W

FARM COPELAND "B" NO. 1


LOC. SE, NW, NW

TOTAL DEPTH 4331'

COUNTY STAFFORD CO., KANSAS

COMM. October 11, 1959 COMP. October 23, 1959

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 263' W/225 sax.

ELEVATION 1960' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

160	Sand & gravel
215	Sand
263	Red bed
850	Shale
875	Anhydrite
1525	Shale
1825	Shale w/lime streaks
2350	Lime
3278	Shale & lime
3700	Lime & shale
4083	Lime
4107	Lime & chert
4172	Shale
4246	Chert
4310	Lime & shale
4331	Arbuckle
4331	T. D.

RECEIVED
COMMISSION

NOV-9 1959

CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS
County of BARTON } ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 COPELAND "B" well.

Verne A. Morris

Subscribed and sworn to before me this 5th day of November 1959

My Commission Expires: April 14, 1963

Arthur G. Miller
NOTARY PUBLIC