

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202



5-12

2-090468

API NUMBER: 15-155-21,400-0000

C NE NE SW, SECTION 27 TOWNSHIP 25 RANGE 9W

OPERATOR LICENSE # 5210 2310 FEET FROM S SECTION LINE
OPERATOR LEBSACK OIL PRODUCTION INC 2970 FEET FROM E SECTION LINE
NAME & P.O. BOX 489
ADDRESS HAYS, KS 67601

LEASE NAME: BAILEY #1-27
COUNTY: RENO 128.86
WELL TOTAL DEPTH: 3965'
PIPE:
SURFACE CASING: 8 5/8" @ 234' - 150 SX

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE

ADDRESS: P.O. BOX 209, CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 8 MONTH: 5 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MIKE

COMPANY NAME: MIKE'S TESTING & SALVAGE PHONE: (316) 938-2943

WERE: SAND TO 3740', CAP WITH 5 SACKS OF CEMENT.

SHOOT FOR RECOVERY.

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART { X } NONE ()

COMPLETED: HOUR: 15:00 DAY: 12 MONTH: 5 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED TO 3740', CAPPED WITH 5 SACKS OF CEMENT. RECOVERED 3100' OF 5 1/2". THRU 5 1/2" SPOTTED 35 SACKS OF CEMENT AT 1350', 35 SACKS AT 750', AND CIRCULATED FROM 300' TO SURFACE.

REMARKS: 60/40 POZ 4% GEL 200 SACKS CEMENT & 300#s HULLS ALLIED #6503

RECEIVED
KANSAS CORPORATION COMMISSION

I DID OBSERVE THIS PLUGGING.

Ralph Tittel
RALPH TITTEL

INVOICED

DATE MAY 20 1997

INV. NO. 48146

MAY 20 1997
5-20-97
CONSERVATION DIVISION
WICHITA, KS

FORM CP-2/3

REV. 3/90

5-12