

9-17

RECEIVED  
KANSAS CORPORATION COMMISSION

OCT 13 1993  
10-13-93  
CONSERVATION DIVISION  
WICHITA, KS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-155-21,220-00-00  
N/2 SE SE, SECTION 23 TOWNSHIP 24 RANGE 5W

OPERATOR LICENSE # 5663 990 FEET FROM S SECTION LINE  
660 FEET FROM E SECTION LINE

OPERATOR HESS OIL COMPANY  
NAME & P O BOX 1009  
ADDRESS MCPHERSON, KS 67460

LEASE NAME: BONTRAGER #1  
COUNTY: RENO  
WELL TOTAL DEPTH: 3860' 125.45  
CONDUCTOR PIPE: 10-3/4" @ 339'  
SURFACE CASING: 8-5/8" @ 626'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SMD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: HESS OIL COMPANY  
ADDRESS: PO BOX 1009, MCPHERSON KS 67460 LICENSE: 5663

COMPANY TO PLUG AT: HOUR: 8:30 DAY: 17 MONTH: 9 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: JAMIE HESS  
COMPANY NAME: HESS OIL COMPANY PHONE: 316-263-2243

WERE: SAND TO 3345' & TOP W/5 SX CMT - SHOOT OFF PIPE & PULL  
TO 675' & SPOT 50 SX CMT - PULL REMAINING PIPE & SHOOT  
OFF PIPE & PULL TO 300' - CIRC CMT FROM 300' TO SURF  
PERFS @ 3395'-3401'  
5-1/2" CSG @ 3523'

PLUGGING PROPOSAL RECEIVED BY: JOHN SANDERS

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 16:00 DAY: 17 MONTH: 9 YEAR: 1993

ACTUAL PLUGGING REPORT:  
SANDED TO 3345' & TOPPED W/5 SX CMT - CUT 5-1/2" CSG  
OFF @ 2035' & PULLED TO 675' & SPTD 50 SX CMT - PULLED  
REMAINING 5-1/2" - CUT 8-5/8" CSG @ 310' & CIRC 110 SX  
CMT TO SURF - RETRIEVED 2035' OF 5-1/2" CSG & 310' OF  
8-5/8" CSG - THIS WELL WAS TESTED BUT NEVER PRODUCED.

REMARKS: USED 60/40 POZ W/8% GEL BY ALLIED #6489

I DID NOT OBSERVE THIS PLUGGING.

INVOICED

DATE OCT 19 1993

19  
MICHAEL R. WILSON (AGENT)

INV. NO. 38965

aw 9-17