

8-4

2-070780

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API Number: 15-155-21125

NW NW NW SECTION 12 TWP 26 RANGE 06W

OPERATOR LICENSE # 5808 4950 FEET FROM S SECTION LINE
OPERATOR W.R. ALLAM 4950 FEET FROM E SECTION LINE
NAME & P.O. BOX 2325
ADDRESS HUTCHINSON, KS 67504

LEASE NAME BETTY KREHBIEL #1
COUNTY RENO
WELL TOTAL DEPTH 4018' 130.59
PIPE 5 1/2" @ 4018'
SURFACE CASING 8 5/8" @ 218'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SUNFLOWER WELL SERVICE

ADDRESS: 408 N. 4TH, CANTON, KS 67428 LICENSE: 30280

COMPANY TO PLUG AT: _____ HOUR: 10:00 DAY: 3 MONTH: 8 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM: BUD

COMPANY NAME: SUNFLOWER WELL SERVICE PHONE: (816) 628-4723

WERE: SAND TO 3200' - 5 SKS
35 SKS - 1150'
35 SKS - 650'
270' TO 0

RECEIVED
KANSAS CORPORATION COMMISSION

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI AUG 11 1998

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL PART NONE 8-11-98

COMPLETED: HOUR: 1:00 DAY: 4 MONTH: 8 YEAR: 1998

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 3200' AND 5 SKS OF COMMON. SHOT 5 1/2" CASING OFF AT 2500'. PULLED TO 1150' AND PUMPED 35 SKS. PULLED TO 650' AND PUMPED 35 SKS. PULLED TO 270'. CIRCULATE CEMENT TO SURFACE.

REMARKS: UNITED #5395 60/40 POZ, 4% GEL

I DID OBSERVE THIS PLUGGING.

Jack Luthi
JACK LUTHI

FORM CP-2/3
REV. 3/90

INVOICED
DATE AUG 12 1998
INV. NO. 51149