

2 100218

5-21-87

API NUMBER 15- 155-20,839-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW SW, SEC. 16, T 26 S, R 8 W/EX
_____ feet from S section line
_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6593

Lease Name Lubbers Well # 2

Operator: Coastal Oil and Gas Corporation
Name & Address: One Leadership Sq., Ste. 1700
Oklahoma City, OK 73102
405-239-7031

County Reno 139.43
Well Total Depth 4290 PBD 4012 feet
Conductor Pipe: Size 4 1/2 feet 4012
Surface Casing: Size 8 5/8 feet 268

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated Perforated from 3915-3917

Plugging Contractor Great Bend Casing Pulling License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: AM Day: 19 Month: 5 Year: 19 87

Plugging proposal received from Don De Herrera/ Mike Gomez
Halliburton

(company name) Great Bend Casing Pulling (phone) 316-793-9711

work: Dump sand plug capped with five sacks cement at 3910'. P.O.O.H. with 2 3/8"
tubing. Perforate 4 1/2" casing at 270'. Circulate 76 sacks 60/40 poz cement in
4 1/2" casing adn annulus from 270-3'. Cut 8 5/8 and 4 1/2 casing 3' B.G.L.

Plugging Proposal Received by John Sanders.
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:30 Day: 21 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT Pump well to 2000# to kill PSI of 1400#, pulled tubing. Pump
one sack of hulls and 35 sacks cement. 2% cc on bottom. Shot 4 1/2" and pulled
61 joints - tagged - then pumped 400# hulls, 10 sakcs gel, 25 sacks cement, 10 sacks
gel, 100# hulls, and 100 sacks cement. Shut in well.

MAY 28 1987
5-28-87
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied Cement #2575 and #2572 60/40 poz, 4% gel, 700# Oper 600# SI
(If additional description is necessary, use BACK of this form.)

INVOICED

(copy to _____) observe this plugging.

DATE 6-2-87

Signed J. C. Sanders
(TECHNICIAN)

INV. NO. 17079