

2 100225

MAY 14 1987

API NUMBER 15- 155-20,741- 0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NW SW , SEC. 16 , T 26 S, R 8 W/EX

_____ feet from S section line

_____ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6593

Lease Name Vincent-Lubbers #1

Operator: Coastal Oil and Gas Corporation
Name &

County Reno 140.56

Address One Leadership Sq., Ste. 1700

Well Total Depth 4325 PBD 3450 feet

Oklahoma City, OK 73102

Conductor Pipe: Size 4 1/2 feet 3454

405-239-7031

Surface Casing: Size 8 5/8 feet 317

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated Perforated from 3370-3374

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address Great Bend, KS

Company to plug at: Hour: 3:00 Day: 14 Month: 5 Year: 19 87

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers (phone) _____

were: Dump sand plug capped with five sacks cement at 3360'. POU it with 2 3/8" tubing, perforate 4 1/2" at 325' and circulate 92 sacks of 60/40 poz cement in 4 1/2" casing and annulus from 325' to 3'. Cutt off 8 5/8 and 4 1/2" casing 3' below ground level.

Plugging Proposal Received by Warren Kirkpatrick (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:15 Day: 14 Month: 5 Year: 19 87

ACTUAL PLUGGING REPORT Sand bottom to 3300' and top with ten sacks cement. Shot 4 1/2 and pulled. Pumped 500# hulls, 125 sacks cement. Shut in well.

6-5-87

JUN 2 1987

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied #2603 60/40 poz, 4% gel, 500# - oper SI - 100#

(if additional description is necessary, use BACK of this form.)

INVOICED
(if added, observe this plugging.)

DATE 6-3-87

Signed J.L. Sanders (TECHNICIAN)

INV. NO. 17138