

15-155-21151-0000  
9-30 2-100786 132 R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 1-071

~~SW~~ SW SW, SECTION 1 TOWNSHIP 26 RANGE 6W

OPERATOR LICENSE # 5808 495 FEET FROM S SECTION LINE  
4785 FEET FROM E SECTION LINE

OPERATOR W. R. Allam  
NAME & Box 2325  
ADDRESS Haven, KS 67543

LEASE NAME: Grabber Trust #1

COUNTY: Reno  
WELL TOTAL DEPTH: 4035' / 31.14

PIPE: 5-1/2" @ 4034' / 150 sx  
SURFACE CASING: 8-5/8" @ 220' / 120 sx

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: Perfs 3609-08' - 3613-15'

PLUGGING CONTRACTOR: Sunflower Well Service  
ADDRESS: P. O. Box 341, Canton, KS 67428 LICENSE: 30280

COMPANY TO PLUG AT: HOUR: 10:00a DAY: 29 MONTH: 9 YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Bud Davis  
COMPANY NAME: Sunflower Well Service PHONE: 316-638-4723

WERE: Sand 50' above top perf - 5 sx - cmt w/  
shoot & pull pipe - spot cmt from 1000', 35 sx -  
550' 35 sx & circ from 300' to surf.

RECEIVED

NOV 10 1992  
11-10-92

PLUGGING PROPOSAL RECEIVED BY: Sanders

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

CONSERVATION DIVISION  
WICHITA, KS

COMPLETED: HOUR: 8:00p DAY: 30 MONTH: 9 YEAR: 1992

ACTUAL PLUGGING REPORT:  
Sanded to 3550' & dumped 5 sx cmt - shot & pulled  
5-1/2" from 3096' to 1000' - spotted 35 sx cmt - pulled  
5-1/2" to 550' & spotted 35 sx cmt - pulled 5-1/2" to  
300' & circ to surf - topped off well.

REMARKS: Howco #253890 60/40 6%

INVOICED  
IF YOU OBSERVE THIS PLUGGING.

DATE 12-4-92  
INV. NO. 36955  
DEC 11 1992

J. L. Sanders  
J. L. Sanders (AGENT)