

5 040361.

11-6-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 155-20,709-0000

NE NE SW, SEC. 30, T 25 S, R 4 W/XX

2310 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5357

Lease Name Doles Well # 1

Operator: Frank J. Black

County Reno 131.95

Name & Address P.O. Box 250

Well Total Depth 4060 feet

McPherson, KS 67460

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 257 175 SXS

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Nicholas Casing Pulling License Number 6698

Address Geneseo, KS

Company to plug at: Hour: 10:00am Day: 6 Month: 11 Year: 1987

Plugging proposal received from Alan Nicholas

(company name) Nicholas Casing Pulling (phone) 824-6467

were: Sand to 3175 and cap with 5 sxs cement. Recovered 5 1/2". Bail to 375' and set solid bridge. Redimix to 4' from surface.

Plugging Proposal Received by J. J. Sanders (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 12:00pm Day: 6 Month: 11 Year: 1987

ACTUAL PLUGGING REPORT 5 1/2" set @4059. PBDT 3246 Perf 3227-32

Sand to 3175 and cap with 5 sxs cement. Recovered 2200' of 5 1/2" casing.

Bailed to 410'. Set solid bridge and filled to surface with redimix.

RECEIVED STATE CORPORATION COMMISSION

NOV 10 1987

11-10-87

Remarks: Haven Redimix--5 1/2 yards--#7474, Kansas

(If additional description is necessary, use BACK of this form.)

INVOICED

(did / did not) observe this plugging.

DATE 11-13-87

Signed Ralph J. Jett (TECHNICIAN)

INV. NO. 18850 WK