

1030262

R

To:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,072-0000

SW SW SE , SEC. 3 , T 25 S, R 13 W/E
330 feet from ~~XXX~~ section line
2310 feet from ~~XXX~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9585

Lease Name Copeland Well # 1

Operator: Three Bar, Inc.

County Stafford

Name & Address P. O. Box 139

Well Total Depth 4280 139.10 feet

Great Bend, KS 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 408

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Boger Brothers Drilling License Number 9421

Address R. R. 2, Box 88, Hoisington, KS 67544

Company to plug at: Hour: 8:00 pm Day: 23 Month: August Year: 19 84

Plugging proposal received from Gary Davidson

(company name) Boger Brothers (phone) 316-653-4739

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 810' with 50 sx cement

2nd plug at 420' with 40 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement

Plug water well with 5 sx cement

Plugging Proposal Received by Steve Shumant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:00 pm Day: 23 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 810' with 50 sx cement, 2nd plug at 420' with 40 sx

cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with

10 sx cement, 5th plug to circulate rat hole with 10 sx cement, and plugged water well

with 5 sx cement.

9-4-84

RECEIVED
STATE CORPORATION COMMISSION
Remarks: Used 60/40 Pozmix 2% gel, 3% cc, 1% cc, 1% cc, 1% cc
(If additional description is necessary, use BACK of this form.)

SEP 04 1984

INVOICED

DATE 9-12-84

CONSERVATION DIVISION
Wichita, Kansas

Steve Shumant
(TECHNICIAN)

INV. NO. 3647

8-23

FORM CP-2/3
Rev. 01-84