

1050341

API NUMBER 15- 185-22,081-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SW SW, SEC. 4, T 25 S, R 13 W/4
330 feet from ~~N~~ SE Corner of
4290 feet from ~~W~~ SE Corner of

TECHNICIAN'S PLUGGING REPORT

Operator License # 7261

Lease Name Cornwell Well # 1

Operator: Pate-Dombaugh Petroleum

County Stafford

Name & Address 922 Union Center

Well Total Depth 4320 140.49 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 371

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Kaw Drilling Co., Inc. License Number 6739

Address 1010 Union Center, Wichita, KS 67202

Company to plug at: Hour: 3:00 pm Day: 12 Month: September Year: 19 84

Plugging proposal received from Lyle Juergensen

(company name) Kaw (phone) 316-264-0316

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 4285' with 40 sx cement

2nd plug at 806' with 50 sx cement

3rd plug at 420' with 40 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement Plugging Proposal Received by Richard M. Lacy (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:00 pm Day: 12 Month: September Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 4285' with 40 sx cement, 2nd plug at 806' with 50

sx cement, 3rd plug at 420' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement, 7th plug to circulate mouse hole with 10 sx cement. STATE CORPORATION COMMISSION

RECEIVED
SEP 17 1984

Clyde Wiley gave the plugging orders

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc

If additional description is necessary, use BACK of this form.)

(Date) (Time) (Day) (Month) (Year) observe this plugging.

Signed Richard M. Lacy SP (TECHNICIAN)

INVOICED

DATE 9-20-84

INV. NO. 3788