

1121086

11-22

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-185-22,197-0000
SE NE SW, SEC. 9, T 25 S, R 13 W/E
1650 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30852

Lease Name Fisher Farms Well # 1

Operator: KLM Operating

County Stafford

Name & Address P.O. Box 155

Well Total Depth 4401 143.03 feet

Belpre, KS 67519

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 272

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529

Address: P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 9:35 a.m. Day: 22 Month: 11 Year: 1995

Plugging proposal received from Richard McIntyre

(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

were: 5 1/2" at 4325' w/150 sx cement, PBSD 4305', Perfs at 4245-49'

1st plug sand back to 4200' and dump 5 sx cement on top of sand through bailer,

2nd plug at 800' with 50 sx cement,

3rd plug at 300' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Bill Johnson (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:45 a.m. Day: 22 Month: 11 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4197' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 5 sx gel and 60 sx cement at 800',

3rd plug pumped 5 sx gel and 40 sx cement at 300',

4th plug topped off with 10 sx cement.

Also witnessed by Kevin Strube.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2745' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

(If possible, ~~operator~~ observe this plugging.

INVOICED

DATE 12-6-95

Signed Duane Rankin (TECHNICIAN)

INV. NO. 44245

RECEIVED
STATE CORPORATION COMMISSION
DEC - 7 - 1995
CONSERVATION DIVISION
Wichita, Kansas

12-7-95