

1041337

TO: STATE CORPORATION COMMISSION

2-2

21,835.0000  
API NUMBER ~~15-185-21000835~~  
C S/2 SW SE SEC. 7, T 25 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ODELL WELL # 3

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD 144103

OPERATOR LICENSE # 4385

WELL TOTAL DEPTH 4450 FEET

OPERATOR: SABRE PETROLEUM PRODUCTION CSG: SIZE 5 1/2" @ 4340' WITH 175 SX

NAME AND ROUTE #1 SURFACE CASING: SIZE 8 5/8" @ 290' WITH 100 SX

ADDRESS PRESTON, KS 67569

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR PRATT WELL SERVICE INC. LICENSE NUMBER 5893

ADDRESS PO BOX 847, PRATT, KS 67124-0847

COMPANY TO PLUG AT: HOUR: 11:30 AM DAY: 02 MONTH: 02 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM TERRY BAIRD

(COMPANY NAME) PRATT WELL SERVICE, INC (PHONE) 316-672-2531

WERE: PERFS AT 4066-4072

1ST PLUG SANDED BACK TO 3960' AND PUT 5 SX CEMENT ON TOP OF SAND BRIDGE THRU BAILER.

2ND PLUG PUMPED DOWN 8 5/8" SURFACE PIPE WITH 300# HULLS, 10 SX GEL- 50 SX CEMENT- 10 SX

GEL-100# HULLS- 100 SX CEMENT. MAXIMUM PSI AT 400#. SHUT IN AT 250#.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 02 MONTH: 02 YEAR: 1999

ACTUAL PLUGGING REPORT \_\_\_\_\_

1ST PLUG SANDED BACK TO 3960' AND PUT 5 SX CEMENT ON TOP OF SAND BRIDGE THRU BAILER.

2ND PLUG PUMPED DOWN 8 5/8" SURFACE PIPE WITH 300# HULLS, 10 SX GEL- 50 SX CEMENT- 10 SX GEL

100# HULLS- 100 SX CEMENT. MAXIMUM PSI AT 400#. SHUT IN AT 250#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1797' OF 5 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING. KANSAS CORPORATION COMMISSION

SIGNED Stephen J. Perfec  
(TECHNICIAN) FORM CP-2/3

INVOICED

DATE 2-17-99

INV. NO. 60639

FEB 10 1999

CONSERVATION DIVISION  
WICHITA, KS