

1041336
TO: STATE CORPORATION COMMISSION

2-2

API NUMBER 15-185-00822-0000 Completed 1-1955
SW SE SE SEC. 7, T 25 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 990 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ODELL WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY STAFFORD IND. 01

OPERATOR LICENSE # 4385

WELL TOTAL DEPTH 4308 FEET

OPERATOR: SABRE PETROLEUM PRODUCTION CSG: SIZE 5 1/2" @ 4307' WITH NA SX

NAME AND ROUTE #1 SURFACE CASING: SIZE 8 5/8" @ 252' WITH NA SX

ADDRESS PRESTON, KS 67569

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR PRATT WELL SERVICE INC. LICENSE NUMBER 5893

ADDRESS PO BOX 847, PRATT, KS 67124-0847

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 02 MONTH: 02 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM TERRY BAIRD

(COMPANY NAME) PRATT WELL SERVICE, INC (PHONE) 316-672-2531

WERE: PERFS AT 4294-4304 & 3889-3899

1ST PLUG SANDED BACK TO 3736' AND PUT 5 SX CEMENT ON TOP OF SAND BRIDGE THRU BAILER.

2ND PLUG PUMPED DOWN 8 5/8" SURFACE PIPE WITH 300# HULLS, 10 SX GEL- 50 SX CEMENT- 10 SX

GEL-100# HULLS- 100 SX CEMENT. MAXIMUM PSI AT 400#. SHUT IN AT 200#.

RECEIVED
FEB 10 1999

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

CONSERVATION DIVISION
PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 10:45 AM DAY: 02 MONTH: 02 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SANDED BACK TO 3736' AND PUT 5 SX CEMENT ON TOP OF SAND BRIDGE THRU BAILER.

2ND PLUG PUMPED DOWN 8 5/8" SURFACE PIPE WITH 300# HULLS, 10 SX GEL- 50 SX CEMENT- 10 SX GEL

100# HULLS- 100 SX CEMENT. MAXIMUM PSI AT 400#. SHUT IN AT 200#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1936' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Stephen J. Barber
(TECHNICIAN) FORM CD-2/3

DATE 2-17-99

INV. NO. 60639