

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: ~~15-185-19010-00-01~~
Spot: NWSENW Sec/Twnshp/Rge: 12-25S-13W
2100 feet from S Section Line, 2530 feet from E Section Line
Lease/Unit Name: NORTH LEEsburg Well Number: 403
County: STAFFORD Total Vertical Depth: 4145 feet

Operator License No.: 6679
Op Name: SHORT, W.D. D/B/A SHORT, W. D. OIL
Address: PO BOX 1
OXFORD, KS 67119

Production Casing Size: 5.5 feet: 4144 WITH 200 SX CMT
Surface Casing Size: 8.625 feet: 319 WITH 175 SX CMT

\$ 134.71

Well Type: EOR UIC Docket No: E11122.4 Date/Time to Plug: 07/18/2003 1:00 PM
Plug Co. License No.: 6679 Plug Co. Name: SHORT, W.D. D/B/A SHORT, W. D. OIL CO.
Proposal Rcvd. from: DAVID CRAMER Company: SHORT, W.D. D/B/A SHORT, W. D. Phone: (620) 455-3576

Proposed Plugging Method: SAND BACK TO 3625' WITH 5 SX CMT. PLUG AT 750' WITH 10 SX GEL & 50 SX CMT. PLUG AT 350' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/18/2003 2:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 4079-92'. SANDED BACK TO 3625' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 2 3/8" TUBING. 1ST PLUG AT 750' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 350' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
JUL 25 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY UNITED CEMENTING. RECOVERED 1280' OF 5 1/2" CASING.

Plugged through: TBG

District: 01

RECEIVED
JUL 21 2003
KCC Dodge City

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

DATE 7-25-03

INV. NO. 20040161

Form *CF 2/03*