

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-19020-00-01  
Spot: SEWNNE Sec/Twnshp/Rge: 13-25S-13W  
990 feet from N Section Line, 1650 feet from E Section Line  
Lease/Unit Name: SOUTH LEESBURG UNIT Well Number: 202  
County: STAFFORD Total Vertical Depth: 4120 feet

Operator License No.: 6679  
Op Name: SHORT, W.D. D/B/A SHORT, W. D. OIL  
Address: PO BOX 1  
OXFORD, KS 67119

Production Casing Size: 6 feet: 4109 WITH 225 SX CMT  
Surface Casing Size: 10.75 feet: 280 WITH 225 SX CMT

\$ 133<sup>90</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/16/2003 11:00 AM  
Plug Co. License No.: 6679 Plug Co. Name: SHORT, W.D. D/B/A SHORT, W. D. OIL CO.  
Proposal Rcvd. from: DON SHORT Company: SHORT, W.D. D/B/A SHORT, W. D. Phone: (620) 455-3576

Proposed Plugging Method: SAND TO 3000' & 6 SX CMT. PLUG AT 750' WITH 20 SX GEL & 80 SX CMT. PLUG AT 300' WITH 80 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 10/16/2003 1:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:


PBTD 3600'. PERFS AT 3057-3069'. SANDED TO 3000' & 6 SX CMT WITH DUMP BAILER. 1ST PLUG AT 750' WITH 20 SX GEL - 80 SX CMT. 2ND PLUG AT 300' WITH 80 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

RECEIVED  
OCT 22 2003  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY UNITED CEMENTING. RECOVERED 1150' OF 6" CASING.

Plugged through: TBG

District: 01



Signed

*Richard W. Lucy*

(TECHNICIAN)

INVOICED

DATE 10-22-03  
NO. 2004060658

Form CP-28