

To: **1 031074**
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 30217

Operator: Robba Exploration, Inc.
Name & Address 230 North Market
Wichita, KS 67202

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒

Other well as hereinafter indicated ☐

Plugging Contractor Allen Drilling Company License Number 5422

Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 4 a.m. Day: 1 Month: 5 Year: 19 90

Plugging proposal received from Craig Christopher

(company name) Allen Drilling Company (phone) 316-793-3582

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 756-773'

1st plug at 790' with 50 sx cement,

2nd plug at 300' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All ☐ Part ☐ None ☒

Operations Completed: Hour: 6:30 a.m. Day: 1 Month: 5 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 790' with 50 sx cement,

2nd plug at 300' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-16-90

INV. NO. 28169

MAY 13 1990
GIVEN TO
WICHITA, KANSAS

Signed Steve Durrant
(TECHNICIAN)

FORM MUST BE TYPED
FORM C-1 12/88

EFFECTIVE DATE: 4/23/90

State of Kansas

185-22,668

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date April 22 1990
month day year

Sec. 14 Twp 25 S, Rg 15 East
West

OPERATOR: License # 30217
Name: Robba Exploration, Inc.
Address: 230 N. Market
City/State/Zip: Wichita, Kansas 67202
Contact Person: Richard A. Robba
Phone: (316) 264-6653

330 feet from South line of Section
1650 feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License # 5422 269-9432
Name: Allen Drilling Company

County: Stafford
Lease Name: Dwight Russell Well #: 1
Field Name: Leiss
Is this a Prorated Field? yes X no
Target Formation(s): Lansing, Arbuckle
Nearest lease or unit boundary: 330'
Ground Surface Elevation: 1924 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 200
Depth to bottom of usable water: 200
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 220
Length of Conductor pipe required: None
Projected Total Depth: 4400
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:
well farm pond X other
DWR Permit #: To be provided by contractor
Will Cores Be Taken?: yes X no
If yes, proposed zone: 220' Alt. IReq.

Well Drilled for: Well Class: Type Equipment:
X Oil ... Inj X Infield X Mud Rotary
... Gas ... Storage ... Pool Ext. ... Air Rotary
... OAWO ... Disposal ... Wildcat ... Cable
... Seismic; ... # of Holes

If OAWO: old well information as follows:
Operator: ...
Well Name: ...
Comp. Date: ... Old Total Depth ...


Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location: ...

Exp. 10/18/90

AFFIDAVIT

PUSHER Craig Christopher
TD 4328 FORMATION Arb 4302
SURFACE PIPE 266 @ 8 5/8
ANHYDRITE 756-773 ELEVATION ...
STARTING TIME & DATE 4:00 AM 5-1
COMPLETION TIME & DATE 6:30 AM 5-1
1st PLUG @ 790 FT. W/ 50 SX
2nd PLUG @ 300 FT. W/ 50 SX
3rd PLUG @ 40 FT. W/ 10 SX
4th PLUG @ ... FT. W/ ... SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ -0- SX
WATER WELL PLUGGED W/ hardness SX
CEMENT COMPANY Holabarton
TECHNICIAN SD
TYPE OF CEMENT 60/40 6%
Pit Status Remove Free Fluid
chlorides

Spud 4-24-90
Surf ± 300
Water well



APR 19 1990
MAILED
REGISTRATION DIVISION
Wichita, Kansas

Spud date: ... Agent: ...