

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-155-20,898-0000  
NE/4, Sec. 23, T 25 S, R 8 W/E  
1980 feet from N/S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 505.3

Lease Name Krehbiel Well # 1

Operator: Petro-Dynamics Corporation  
Name & Address 555 N. Woodlawn  
Building #1, Suite 207  
Wichita, Kansas 67208

County Reno  
Well Total Depth 3870 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 279'

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor KANDRILCO LTD. & Sun Oilwell License Number 5887 Reg # 436  
Address 555 N. Woodlawn, Bldg. 1, Ste 207, Wichita, Kansas 67208

Company to plug at: Hour: 1:00 AM Day: 26 Month: October Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Larry Hicks  
(company name) KANDRILCO LTD. (phone) 316 375 4086

were: Fill hole with mud. Pump 50 sacks cement through drill pipe at 310'. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.  
Cement Rathole with 10 sacks cement.  
Cement Mousehole with 10 sacks cement.

Signed [Signature] (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:30 AM Day: 26 Month: October Year: 1982

ACTUAL PLUGGING REPORT Hole filled with mud. 50 sacks cement pumped through drill pipe at 310'. Hole filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement.  
Rathole cemented with 10 sacks cement.  
Mousehole cemented with 10 sacks cement.

Remarks: Cement used: 50/50 Permox w/ 2% gel and 3% C.C.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe the plugging.

RECEIVED STATE CORPORATION COMMISSION

NOV 3 1982

CONSERVATION DIVISION Wichita, Kansas

Signed [Signature] (TECHNICIAN)

FORM CP-2/3 Rev. 9-82

INVOICED

DATE 11-16-82

INV. NO. 1612-W