

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-21128-00-00  
Spot: N2SWNW Sec/Twnshp/Rge: 18-17S-29W  
3630 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: GRUSING Well #: 1  
County: LANE Total Vertical Depth: 4650 feet

Operator License No.: 30481  
Op Name: APOLLO ENERGIES, INC.  
Address: 10378 N 281 HWY  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
PC		2162		WITH 500 SX CMT
PROD	4.5	4597	0	WITH 150 SX CMT
SURF	8.625	474		WITH 265 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/18/2015 4:30 PM  
Plug Co. License No.: 30481 Plug Co. Name: APOLLO ENERGIES, INC.  
Proposal Rcvd. from: JIM BYERS Company: APOLLO ENERGIES, INC. Phone: (620) 672-5071

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: NONE  
Date/Time Plugging Completed: 09/18/2015 7:00 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

SAND BACK TO 4290' WITH 4 SX CMT ON TOP. 1ST PLUG AT 2250' WITH 35 SX CMT & 100# HULLS. 2ND PLUG AT 1200' WITH 50 SX CMT & 200# HULLS. PERFORATE AT 525'. RUN TBG TO 525' & CIRCULATE CMT INSIDE & OUT TO SURFACE WITH 190 SX CMT. PULL TBG. TOP OFF WITH 3 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4342	4346		

OCT 09 2015

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED  
SEP 25 2015  
KCC DODGE CITY

Signed \_\_\_\_\_

(TECHNICIAN)

KCC WICHITA

OCT 02 2015

RECEIVED