

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-081-22123-00-00  
Spot: S2SWNE Sec/Twnshp/Rge: 1-27S-33W  
2310 feet from N Section Line, 1980 feet from E Section Line  
Lease Name: LEONA UNIT Well #: 11-1  
County: HASKELL Total Vertical Depth: 256 feet

Operator License No.: 34318

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	0	0	0	0

Op Name: BEREXCO LLC

Address: 2020 N. BRAMBLEWOOD  
WICHITA, KS 67206

Well Type: LH

UIC Docket No:

Date/Time to Plug: 08/29/2015 12:00 AM

Plug Co. License No.: 34317

Plug Co. Name: BEREDCO LLC

Proposal Rcvd. from: EVAN MAYHEW

Company: BEREXCO LLC

Phone: (316) 265-3311

Proposed  
Plugging  
Method:

PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KENNY SULLIVAN

Witness Type: PARTIAL

Date/Time Plugging Completed: 09/09/2015 12:00 AM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

LOST CIRCULATION AT 256'. 8/29/15: PUMPED 100 SX CLASS A 3% CC AT 230', 50 SX 65/35 POZMIX 6% GEL 3% CC & 50 SX CLASS A 3% CC AT 60'. TD 96' FROM SURFACE. 9/2/15: DUMPED 100 SX CLASS A 3% CC WITH 700# HULLS. WAITED 2 HOURS & TAGGED 85' DOWN. DUMPED 200 SX CLASS A 3% CC WITH 750# HULLS. TAG TD 60' DOWN. 9/3/15: TD 60' FROM SURFACE. NO FLUID. 9/9/15: TAG TD @ 60' FROM SURFACE. PUMP 9 YARDS READY MIX & FILLED TO SURFACE.


Remarks: CEMENT DONE BY ALLIED.

OCT 09 2015  
CKM

Plugged through: DP

District: 01

Signed



(TECHNICIAN)

RECEIVED  
SEP 28 2015  
KCC DODGE CITY

KCC WICHITA

OCT 02 2015

RECEIVED